



PAUL DACUNHA
ARCHITECT INC

Date: June 23, 2021
Project: Interior Alterations at TPL – Maryvale Branch
Parkway Mall (TPL 019--2020)
85 Ellesmere Road Unit 21 and 22
Toronto, ON
Project No.: 20019
Client: Toronto Public Library

Addendum No.5

This Addendum becomes part of the Contract Documents and will be considered to have been included in the tender. Additions, deletions and/or revisions shall be incorporated in the Contract Documents as hereinafter described. The following listings and documents comprise this Addendum.

MISCELLANEOUS QUESTIONS FROM BIDDERS

(Repetitive question have been deleted. Questions that have not been included below may be answered on future addendum.) **(The reply to a question is indicated in bold letters within the brackets.)**

1. Please see drawing A01.2 that states “Provide new HSS steel beam and columns to support the sliding doors. Contractor to provide shop drawings related to metal structure above ceiling and posts/footings to support sliding door assembly designed and stamped by a professional structural engineer licensed in the province of Ontario for review by architect prior to construction(typ)” It is unclear if we need to remove slab on grade and provide new footings. We would like to ask for cash allowance to be provided for this item since it is difficult to provide accurate pricing before the drawings are completed by structural engineer.

(Include the following structural elements

1. **42” x 42” x 12” thk. Concrete footings under each column.
Cut the existing slab and excavate as required in order to provide footing.**
2. **(2) 4” x 8” x .5” HSS columns.**
3. **W 12 x Steel Beam across the top of the column.**
4. **Include for the Structural Engineer design/stamp drawing and the Engineers final review for this work.**

2. Elevation drawings A2.7, A2.8 and A2.9 show “RUB 1” finish on walls. Please provide specifications for product.

(The Rubber wall surface is as follows:

**MANUFACTURER: JOHNSONITE
COLLECTION: MICROTONE
COLOUR: HNSP-LB9 (RAINSTORM)
(HAMMERED TEXTURE)
SIZE: 24”X24”.)**

3. Please provide floor finish for Dock/Storage room. Drawing 3/A01.1 show “Concrete”. Should we include for any floor finish for this room?

(The floor in this room will remain in concrete as is.)



PAUL DACUNHA
ARCHITECT INC

Date: June 23, 2021
Project: Interior Alterations at TPL – Maryvale Branch
Parkway Mall (TPL 019--2020)
85 Ellesmere Road Unit 21 and 22
Toronto, ON
Project No.: 20019
Client: Toronto Public Library

Addendum No.5

This Addendum becomes part of the Contract Documents and will be considered to have been included in the tender. Additions, deletions and/or revisions shall be incorporated in the Contract Documents as hereinafter described. The following listings and documents comprise this Addendum.

4. Please provide specifications for corner guards. Is it plastic or stainless steel?

(The corner guards are required to be stainless steel.)

5. There are three continuous runs that have a Type B, a Type B1, and a Type D, which would be 13' pendant, and 8' recessed (21' total). Do you know if they want this to be seamless, or should there be a break in between the pendant and recessed portion?

(The joints between light are to be seamless.)

DOOR HARDWARE

1. **(Include in the bid price the hardware listed in the Hardware Schedule. Refer to the Hardware Schedule prepared by Trillium Hardware dated June 22, 2021, consisting of 12 pages and attached to this addendum.)**

END OF ADDEDNUM No.5
Consisting of 2 written pages.
Hardware Schedule 12 pages