Michael Pacholok
Chief Procurement Officer

Purchasing and Materials Management Division
City Hall, 18th Floor, West Tower
100 Queen Street West
Toronto, Ontario M5H 2N2

Sabrina Dipietro
Manager, Purchasing Client Services,
Infrastructure & Development Services (IDS)
Purchasing & Materials Management

September 9, 2021

Via Ariba internet posting
(3 Pages)

ADDENDUM No. 3
REQUEST FOR TENDER ARIBA Doc3116480059
CLOSING DATE (REVISED): 12:00 NOON (LOCAL TIME), September 21, 2021

For: Toronto Accessibility Upgrades – Group 08 at Toronto

Please refer to the above Tender Call document in your possession and be advised of the following information:

1. REVISIONS:

The Closing Date for this call has been extended from September 14 to **September 21, 2021**. The question period for this call has ended.

2. QUESTIONS:

Q1 – Finch Yard- Building B
Drawing-A2411, Mentioned verify the dimension of door Openings 1067 and 1015, while Door schedule A9001 shows, the doors are existing and to remain existing.

Since there is no site visit arranged, we cannot know if we have to place new door and frame for required opening size

A1 – That's correct, the doors are existing to remain the note is rather generic the size of the door won't make any difference here so it can be ignored. And for clarity the door panel is 915 but the door plus the frame is 1015 that's why there's that discrepancy.

Q2 – Can we have a site visit to look at the elevator electrical prints to see if Fire Service is existing or if provisions are existing?

A2 – The City will not be hosting site visits for this call.

Q3 – Can we have the laminate colour for the existing panels in each elevator to match it with the new panels below the mirror?

A3 – We do not have specs for existing laminate colour. Only photos

Q4 – Are all tactile floor markers to be replaced, or just add them as required?

A4 – Added as required, please.

Q5 – Elevator Exterior Controls: Do they want a phone & phone pushbutton in the hall station? If yes, which stations, all or only the main ones?

A5 – Exterior buttons are not required to change – only braille required for existing buttons.

Q6 – Phase I key switch is located in the hall station, not Phase II. Please confirm that FEO Phase I manual recall is required.

A6 – No change to be made here.

Q7 – Are hoistway access switches existing in the hall stations?

A7 – No change to be made here.

Q8 – Do they want to add Communication failure and reset key switch in the main hall stations?

A8 – No change to be made here

Q9 – Elevator Interior controls: Usually the Fire Service Phase II key switch is inside the FEO cabinet. Do they want it placed inside the cabinet with the Phase II controls?

A9 – Inside cabinet is preferred. Same design as Elev A can be followed.

Q10 – Do they want a digital car position indicator in the station?

A10 – Yes, that is correct.

Q11 – Do they want a lockable service cabinet below the HELP and ALARM buttons?

A11 – Yes – Similar to Elev A design.

Q12 – Do they want a lexan cover for card reader?

A12 – Lexan cover is required and only for Elevator B. Elevator A does not have a card reader.

Q13 – Elevator A looks like it has newer interior controls with hands free telephone. Do you want it replaced?

A13 – No changes required to controls for elevator A – only mirrors on back wall.

Q14 – Elevator B looks like it has 1 piece handrail around all 3 walls. As the handrail has be to removed to access the rear wall, can you revise the scope to include new handrails on all 3 walls?

A14 – Yes – revised scope to include new handrails on Elevator B to match Elevator A handrail.

Q15 – For accessibility, do they want to add a voice annunciator and car direction indicators in both sides of the car door jambs to the scope of work?

A15 – Yes – please include for this work. Drawings to be updated.

Q16 – Could a clear specification, ie Division 14 be written with the expectations for this work? Adding Fire Service may entail upgrading the elevator controller if it is not already existing.

A16 – No changes to Fire Service. Panel elevations were examples only and meant for high lighting buttons height and braille requirements.

Q17 – It shows Elevator plans & Elevations on drawing G08-229-A5311 at 4330 Dufferin ST, but no spec for elevators, please review and advise.

A17 – We are only changing the panel and adding a mirror for this elevator, that's why we are not specifying an elevator for this building.

3. ATTACHMENTS:

1) 122260-TAU-8-13-1026FINCH_D-M
2) 122260-TAU-8-229-4330DFRN-A-5311

Please continue to monitor this procurement as further extensions or possible cancellation may occur. Please see **www.toronto.ca/covid19** for more information on the City's response. Should you have any questions regarding this addendum send via the event message board or contact Max Parker by email at **Max.Parker@toronto.ca.**

Bidders must acknowledge receipt of all addenda on the space provided on the submission form as per the Process Terms and Conditions, Part 1.7 - Addenda, of the RFT document. All other aspects of the RFT remain the same.

Sincerely,

Clarman Yang

Clarman Yang
Supervisor, Corporate Purchasing
Purchasing and Materials Management Division