

April 21, 2022

Via Ariba internet posting
(3 Pages)

ADDENDUM No. 7
REQUEST FOR TENDER ARIBA Doc3398579373
CLOSING DATE (REVISED): 12:00 NOON (LOCAL TIME), April 26, 2021

For: Toronto Accessibility Upgrades – Group 29 at Toronto, Ontario

Please refer to the above Tender Call document in your possession and be advised of the following information:

1. QUESTIONS

Q1: Please note that Margaret's Housing-301 Broadview Ave.-Drawing A2101-Demo shows only door hardware to be replaced while A2401 mentions to install new doors. Please clarify.

A1 - Information on Dwg. A2401 should be as follow,
Door 104, 107, 109 & 110 should be Note "J". These doors are to only receive hardware upgrades.

Q2: Addendum 4 - A2 Clarification requested for the items Office trailer, portable washroom trailers - respectfully this items are provided on temporarily as part of the general conditions and usually removed from the site after project Completed. Please confirm this items are not to be removed from site after project completion and would have left permanently. Portable ramp (item 2.6) may have to be removed as well after work completion as permanent ramp may have been Constructed.

A2 - Temporary office and washroom trailers are to be provided to accommodate building staff during construction and are to be removed from site as per notes on drawings."

Q3: 843 Palmerston Ave:

Is the window beside door 126b Hollow metal frame or Aluminum?

A3 – It is Hollow Metal.

Q4: Elevation for door 102 is missed.

A4 - See below photo of existing assembly. New assembly to match. Refer to door schedule and to door types on G1004 (*note that this is a rated assembly*)



Q5: 255 Spadina Ave:

Entrance doors 101A-D are aluminum doors but elevation shows glass door.

A5 – Doors 101a, 101b, 101c and 101d are Type 'L' per Door schedule. Refer to door types on G1004

Q6: 765 Queen Street: 1- Door 102A is missed from the door schedule.

A6 - Door 102A is missed from the door schedule.
QueenE does not have a door #102A.

Q7: Drawing D1401 calls for powder coated guards and handrails. This process cannot be done on site due to welding. We recommend painting the handrails.

A7 - Where welding on site is required for situations where installation of replacement handrails is to existing in-situ elements, painting is acceptable as a finish.
All connections are to be grinded and smoothed prior to paint finish.
Powder coating to be used in all other situation.

Please continue to monitor this procurement as further extensions or possible cancellation may occur. Please see www.toronto.ca/covid19 for more information on the City's response. Should you have any questions regarding this addendum send via the event message board or contact Max Parker by email at Max.Parker@toronto.ca.

Bidders must acknowledge receipt of all addenda on the space provided on the submission form as per the Process Terms and Conditions, Part 1.7 - Addenda, of the RFT document. All other aspects of the RFT remain the same.

Sincerely,

Clarman Yang

Clarman Yang
Supervisor, Corporate Purchasing
Purchasing and Materials Management Division