GPY+
Associates Engineering Inc.
90C Centurian Drive, Suite #6,
Markham, ON, L3R 8C5

Tel: (905) 475-3138
Fax: (866) 853-3732
sherwin@gpyengineering.com
engineering@gpyengineering.com

Addendum M-1

Date: July 18, 2022

To: G. Bruce Stratton Architects

Attention: **Ms. Stephanie Kamburis**

Project: York Region Administrative Centre
4th Floor Block A, B, D & E Renovations
17250 Yonge Street
Newmarket, Ontario

Project no. 9907

Subject: Mechanical changes and/or additions

The Contractor is hereby instructed with the following changes/clarifications to the contract documents as described below. All materials and workmanship are to be as described in the contract documents unless stated otherwise.

Title: Mechanical changes. **References:** Mechanical Drawings (**Project # 9907**)

Description of Work:

MECHANICAL DRAWINGS:

1. **Drawing M-103 - Schematic Diagram (Revised, Not Issued):**

1.1 *Detail No. 1, 2, 3 & 4:* Added "**Thermostat Manual Control Operation ("ON" & "OFF" buttons)**".

1.1.1 *"ON" button: press once, activates lighting & fan coil unit. Fan coil unit will operate in occupied state, and will condition space at occupied space temperature set for 1 hour within the corresponding zone.*

1.1.2 *"ON" button: press again within the 1 hour time frame, resets the 1 hour countdown for the corresponding zone.*

1.1.3 *'OFF" button: press once, reverts fan coil unit back to unoccupied state mode and maintain the unoccupied space temperature set. Turns lighting off after 30 seconds.*

Issued by,

Sherwin Reyes .
GPY + Associates Engineering Inc.