

CITY OF TORONTO

ACCESSIBILITY UPGRADES

TOUCH AND FEEL INDEX	
SHEET #	SHEET TITLE
T00	COVER PAGE
T01	WASHROOM
T02	WASHROOM ACCESSORIES
T02.1	WASHROOM ACCESSORIES
T03	WASHROOM FIXTURES & DRINKING FOUNTAIN
T04	KITCHEN MATERIALS AND FIXTURES
T05	RESERVED
T06	TACTILE ATTENTION INDICATORS
T07	TEXTURAL & COLOUR CONTRAST WARNING STRIP AND NOSING
T08	DOOR THRESHOLDS



CITY OF
TORONTO
ACCESSIBILITY
UPGRADES



IBI GROUP
175 Galaxy Blvd, Unit 100
Toronto, ON M9W 0C9, Canada
tel 416 679 1930 fax 416 675 4620
ibigroup.com

TOUCH AND FEEL

INTERIOR FIXTURES AND MATERIALS

TOUCH-AND-FEEL DOCUMENT SHOULD BE READ IN CONJUNCTION WITH
DRAWINGS AND SPECIFICATIONS


Project Number: 9119- 19- 0162 / IBI 122260

Date: 2022-11-01

WASHROOM FINISHES	
WASHROOM / SHOWER WALLS	COLLECTION: COLOUR & DIMENSION
CWT-1	COLOUR: ARCTIC WHITE MATTE
	SIZE: 100mm X 400mm (4"X16")
	SUPPLIER: OLYMPIA
WASHROOM / SHOWER WALL ACCENT	MATCH EXISTING
CWT-2	TILE SIZE IS INDICATED ON ROOM FINISH SCHEDULE
WASHROOM / SHOWER WALL ACCENT	COLLECTION: COLOUR & DIMENSION
CWT-3	COLOUR: TAUPE, MATTE
	SIZE: 100mm X 400mm (4"X16")
	SUPPLIER: OLYMPIA
WASHROOM / SHOWER WALL ACCENT	COLLECTION: COLOUR & DIMENSION
CWT-4	COLOUR: DARK GREY MATTE
	SIZE: 100mm X 400mm (4"X16")
	SUPPLIER: OLYMPIA
FLOORS	COLLECTION: MICA, MATTE FINISH
PFT-1 300mm X 610mm (12"X24")	SIZES: PFT-1(12"X24") PFT-1a(6"X6") PFT-1b(12"X12")
PFT-1a 150mm X 150mm (6"X6")	MEETS DYNAMIC COEFFICIENT OF FRICTION
PFT-1b 300mm X 300mm (12"X12")	PREFERRED SUPPLIER: D9 / EMOTION
SHOWER FLOORS	COLLECTION: STI MOSAICO
PFT-2	COLOUR: MID GREY UNGLAZ
	SIZE: 50mm X 50mm (2"X2")
	MEETS DYNAMIC COEFFICIENT OF FRICTION
	SUPPLIER: STONE TILE
FLOORS	MATCH EXISTING
PFT-3	TILE SIZE IS INDICATED ON ROOM FINISH SCHEDULE
FLOORS	COLLECTION: CORE COLLECTION TERRA
PFT-4	COLOUR: 200 SMOOTH (V)
	SIZE: 304.8mm X 609.6mm (12"X24")
	MEETS DYNAMIC COEFFICIENT OF FRICTION
	SUPPLIER: MOSA TILE

NOTE: THE FINISHES PRESENTED ON THIS PAGE ARE THE BASIS OF DESIGN - ANY ALTERNATES ARE SUBJECT TO APPROVAL BY CITY OF TORONTO, PROJECT MANAGER, FACILITY MANAGER AND STAKEHOLDERS

FOR WASHROOMS WHERE ALL FIXTURES AND WALLS ARE BEING REMOVED ONLY




CWT-1




CWT-3



CWT-4



PFT-2



PFT-4




PFT-1



PFT-1a



PFT-1b


































PICTURE 1



PICTURE 2


NOTE: PICTURES ARE ONLY FOR ILLUSTRATION PURPOSES

 <p>SHELF: SHLF GAMCO MS-18 STAINLESS STEEL MIRROR SHELF – 18"</p>	 <p>SOAP DISH: SDI-1 SURFACE MOUNTED, STAINLESS STEEL, TYPE 304 FLANGE. BRADLEY MODEL NO. 901</p>	 <p>SOAP DISPENSER: SD-1 WALL MOUNTED, AUTOMATIC STAINLESS STEEL WITH STAIN FINISH, CLEAR ACRYLIC REFILL INDICATOR WINDOW AND KEY LOCK. BRADLEY 6A00-11.</p>		
 <p>COAT HOOK: CTH-1 B-983 STAINLESS STEEL, 14- GAUGE AUTO-RELEASE CLOTHES HOOK WITH EXPOSED STAIN FINISH, FACEPLATE WITH SLOPED EDGES.</p>	 <p>SOAP DISH: SDI-2 RECESSED MOUNTED SOAP DISH, HEAVY DUTY STAIN FINISH STAINLESS STEEL. BRADLEY MODEL NO. SA16</p>	 <p>SOAP DISPENSER: SD-2 COUNTER MOUNTED, TOUCH FREE, ONE PIECE, CAST BRASS CONSTRUCTION ABOVE DECK, SINGLE MOUNT FOAM SOAP DISPENSER WITH ADJUSTABLE SENSOR. MOEN, MODEL NO. 8560</p>	<p>L-SHAPED GRAB: GRB-1 SATIN FINISH WITH PEENED GRIPPING SURFACE; 18-GAUGE (1.2MM) STAINLESS STEEL TUBING WITH SATIN-FINISH. 38MM OUTSIDE DIAMETER. ENDS ARE HELIARC WELDED TO FLANGES. CLEARANCE BETWEEN THE GRAB BAR AND WALL IS 38MM. 30" X 30" 762MM X 762MM)</p>	<p>L-SHAPED GRAB: GRB-2 SATIN FINISH WITH PEENED GRIPPING SURFACE; 18-GAUGE (1.2MM) STAINLESS STEEL TUBING WITH SATIN-FINISH. 38MM OUTSIDE DIAMETER. ENDS ARE HELIARC WELDED TO FLANGES. CLEARANCE BETWEEN THE GRAB BAR AND WALL IS 38MM. 40" X 30" (1016MM X 762MM)</p>
 <p>COAT HOOK: CTH-2 B-2116 12-GAUGE (2.7mm) CASE HARDENED STEEL. ONE PIECE BRASS CASTING WITH SATIN NICKEL-PLATED FINISH</p>	<p>DRIP TRAY: DT-1 SURFACE MOUNTED DRIP TRAY, BRUSHED FINISH STAINLESS STEEL. SANTRAL MODEL DRIP TRAY NSU 7 SHORT</p> 	 <p>GRAB BAR: GRB-3 SATIN FINISH WITH PEENED GRIPPING SURFACE; 18-GAUGE (1.2MM) STAINLESS STEEL TUBING WITH SATIN-FINISH. 38MM OUTSIDE DIAMETER. ENDS ARE HELIARC WELDED TO FLANGES. CLEARANCE BETWEEN THE GRAB BAR AND WALL IS 38MM. 30" (762MM)</p>	 <p>GRAB BAR: GRB-4 SATIN FINISH WITH PEENED GRIPPING SURFACE; 18-GAUGE (1.2MM) STAINLESS STEEL TUBING WITH SATIN-FINISH. 38MM OUTSIDE DIAMETER. ENDS ARE HELIARC WELDED TO FLANGES. CLEARANCE BETWEEN THE GRAB BAR AND WALL IS 38MM. 36" (914MM)</p>	 <p>GRAB BAR: GRB-5 SATIN FINISH WITH PEENED GRIPPING SURFACE; 18-GAUGE (1.2MM) STAINLESS STEEL TUBING WITH SATIN-FINISH. 38MM OUTSIDE DIAMETER. ENDS ARE HELIARC WELDED TO FLANGES. CLEARANCE BETWEEN THE GRAB BAR AND WALL IS 38MM. 40" (1016MM)</p>
	<p>DRIP TRAY: DT-2 SURFACE MOUNTED DRIP TRAY, BRUSHED FINISH STAINLESS STEEL. SANTRAL MODEL DRIP TRAY NSU 7</p> 			
 <p>MIRROR: MIR 6 MM" FLOAT GLASS, SELECTED FOR SILVERING, ELECTROLYTICALLY COPPER-PLATED BY GALVANIC PROCESS FURNISH UNITS IN TYPE 430 STAINLESS STEEL FRAMING</p>	<p>DRIP TRAY: DT-3 SURFACE MOUNTED DRIP TRAY, BRUSHED FINISH STAINLESS STEEL. SANTRAL MODEL DRIP TRAY NSU 11 TOUCHLESS SHORT</p> 	 <p>BRADLEY 8370-108</p>  <p>ASI 3413-25</p>  <p>BOBRICK GAMCO-125</p> <p>FOLD DOWN GRAB BAR: FD-GRB-1 18 GAUGE SATIN FINISH STAINLESS STEEL FOR SUPERIOR DURABILITY. HEAVY-DUTY SATIN FINISH STAINLESS STEEL. INTEGRAL TOILET PAPER DISPENSER. 30" (762MM)</p>	 <p>BRADLEY 8370-107</p>  <p>BOBRICK B-4998</p> <p>FOLD DOWN GRAB BAR: FD-GRB-2 18 GAUGE SATIN FINISH STAINLESS STEEL FOR SUPERIOR DURABILITY. HEAVY-DUTY SATIN FINISH STAINLESS STEEL. 30" (762MM)</p>	 <p>BOBRICK B-5892</p> <p>BACK REST: BR GRAB BAR: 18-8, TYPE-304 STAINLESS STEEL TUBING WITH STAIN DINISH. BACKREST: 360X160X40MM WHITE COLOURED POLYURETHANE INTEGRAL FOAM</p>
	<p>DRIP TRAY: DT-4 SURFACE MOUNTED DRIP TRAY, BRUSHED FINISH STAINLESS STEEL. SANTRAL MODEL DRIP TRAY NSU 11 TOUCHLESS</p> 			


				 BRADLEY 5425  BOBRICK 2892	 BRADLEY 5424		
<p>PAPER TOWEL DISPENSER & WASTE RECEPTACLE: PTD/WR (SR) SEMI-RECESSED B-38032: 18-8, TYPE 304, HEAVY-GAUGE STAINLESS STEEL. ALL-WELDED CONSTRUCTION.</p>	<p>PAPER TOWEL DISPENSER AND WASTE RECEPTACLE: PTD/WR (R) RECESSED CONVERTIBLE B-3940: 18-8, TYPE 304, HEAVY-GAUGE STAINLESS STEEL. EXPOSED SURFACES HAVE STAIN-FINISH.</p>	<p>PAPER TOWEL DISPENSER AND WASTE RECEPTACLE: PTD/WR (S) SURFACE-MOUNTED B-3699: 18-8, TYPE 304, 22-GAUGE (0.8mm) STAINLESS STEEL. ALL-WELDED CONSTRUCTION. EXPOSED SURFACES HAVE STAIN-FINISH.</p>	<p>HAND DRYER: HNDR DYSON SPRAYED NICKEL 307174-01, NET WEIGHT: 2.9 KG / 6.17 LBS. H:39.3CM X W:19CM X D:10CM</p>	<p>TOILET TISSUE DISPENSER: TPD-1 SURFACE-MOUNTED TYPE - 304, STAINLESS STEEL WITH STAIN FINISH, DOUBLE ROLL YPE, NON-CONTROLLED DELIVERY, TUMBLER KEY LOCKING MECHANISM, AND WIDE VIEWING SLOT.</p>	<p>TOILET TISSUE DISPENSER: TPD-2 SURFACE-MOUNTED CIRCULAR, STAINLESS STEEL WITH STAIN FINISH, JUMBO ROLL, TUMBLER KEY LOCKING MECHANISM, AND VIEWING SLOT.</p>		
				 BRADLEY 5126  BOBRICK B-69997	 BRADLEY 5402  BOBRICK B-2888		
<p>PAPER TOWEL DISPENSER: PTD (S) SURFACE MOUNTED B-2974: TYPE 304, 18 GAUGE STAINLESS STEEL. ALL-WELDED CONSTRUCTION.</p>	<p>PAPER TOWEL DISPENSER: PTD (R) RECESSED B-35903: TYPE 304, HEAVY-GAUGE STAINLESS STEEL. ALL-WELDED CONSTRUCTION. EXPOSED SURFACES HAVE STAIN-FINISH.</p>	<p>PAPER TOWEL DISPENSER: PTD (SM) SURFACE-MOUNTED B-9262: 304 GAUGE, 18 GAUGE (1,2MM) STAINLESS STEEL. ALL HELIARC WELDED CONSTRUCTION WITH WELL DEFINED EDGES AND CORNERS</p>	<p>PAPER TOWEL DISPENSER: PTD (PR) SURFACE-MOUNTED LEVER OPERATED 2497: COVER: CONSTRUCTED OF HIGH-IMPACT PLASTIC. BACK: HEAVY-GAUGE POWDER-COATED STEEL BACK. PUSH LEVER: FIBERGLASS-REINFORCED ABS PLASTIC.</p>	<p>TOILET TISSUE DISPENSER: TPD-3 SURFACE-MOUNTED DOUBLE-ROLL: TYPE-304, STAINLESS STEEL WITH STAIN FINISH, DOUBLE ROLL TYPE, ONE-PIECE SEAMLESS CONSTRUCTION WITH 4 MOUNTING HOLES, 18 GAUGE STAINLESS STEEL HOOD</p>	<p>TOILET TISSUE DISPENSER: TPD-4 SURFACE-MOUNTED: MULTI-ROLL TYPE 22 GUAGE STAINLESS STEEL CABINET AND DOOR WITH STAIN FINISH AND HEAVY ABS ONE-PIECE THEFT RESISTANT SPINDLES</p>		
<div><div></div><div><p>IBI GROUP 175 Galaxy Blvd, Unit 100 Toronto, ON M9W 0C9, Canada tel 416 679 1930 fax 416 675 4620 ibigroup.com</p></div></div>		<div><div></div><div><p>CITY OF TORONTO ACCESSIBILITY UPGRADES CITY OF TORONTO ACCESSIBILITY UPGRADES</p></div></div>		<p>DRAWING TITLE:</p> <p>WASHROOM ACCESSORIES</p>		<p>Project No: 9119- 19- 0162 / IBI 122260</p> <p>Date: 2022-11-01</p> <p>Issue: ISSUED FOR TENDER</p>	<p>NO.</p> <p>T02.1</p>

					
<p>WALL MOUNTED SINK: (BARRIER FREE USE) L1H DECORUM WALL HUNG LAVATORY WITH EVERCLEAN 9024.001EC.020 - VITREOUS CHINA, WHITE FINISH, WITH SINGLE FAUCET HOLE AND OVERFLOW</p>	<p>COUNTER-MOUNTED SINK: L1 WHITE, SELF-RIMMING, REAR/FRONT OVERFLOW, DRILLED FOR 100 MM SUPPLY FITTING. AMERICAN STANDARD "AQUALYN" #0475.047.020 518 X 441 MM</p>	<p>COUNTER-MOUNTED SINK: (BARRIER FREE USE) L2H WHITE, FOR BARRIER FREE USE, SELF-RIMMING WITH SEALANT, OVERFLOW, DRILLED FOR 100 MM SUPPLY FITTING. AMERICAN STANDARD "AQUALYN" #0475.047.020 518 X 441 MM</p>	<p>WALL MOUNTED SINK C/O WITH SHROUD: (BARRIER FREE USE) L3H DECORUM WALL HUNG LAVATORY WITH EVERCLEAN NO. 9134.001EC/0059.020EC SHROUD - VITREOUS CHINA, WHITE FINISH, WITH SINGLE FAUCET HOLE AND OVERFLOW</p>	<p>UNDER-MOUNTED SINK: (BARRIER FREE USE) L4H WHITE, FOR BARRIER FREE USE WITH REAR OVERFLOW AND UNDERMOUNT CLIPS AMERICAN STANDARD OVALYN UNICERSAL ACCESS 9482.000 489 X 400MM</p>	<p>DRINKING FOUNTAIN: DF EZSDWSLK GALVANIZED STEEL WALL MOUNTED, WHEELCHAIR TYPE WATER COOLER WITH STAINLESS STEEL TOP, FRONT AND SIDE MOUNTED PUSH TO OPERATE LEVER(S), SENSOR, TOUCHLESS ACTIVATION WITH AUTO SHUT OFF BOTTLE FILLER, FLEXI-GUARD SAFETY BUBBLER, AND TRAP PACKAGE.</p>
<p>FAUCET: TO BE USED WITH ALL LAVATORY TYPES MOEN ALIGN SENSOR FAUCET - 8559 ELECTRONIC 'NO-TOUCH' HARDWIRED POWERED FAUCET</p>					
					
<p>TOILET: W1H <u>WALL HUNG</u> - WHITE FINISH - VITREOUS CHINA WITH EVERCLEAN ANTIMICROBIAL SURFACE. NO. 3351.101.002</p>	<p>TOILET: W2H <u>FLOOR MOUNTED</u> WHITE FINISH - VITREOUS CHINA WITH EVERCLEAN ANTIMICROBIAL SURFACE. NO. 3461.001.020</p>	<p>TOILET WITH TANK: W3H <u>FLOOR MOUNTED</u> WHITE FINISH - VITREOUS CHINA WITH EVERCLEAN ANTIMICROBIAL SURFACE. PA TANK, 1.1 GPF WHITE</p>		<p>URINAL: U1H WALL HUNG 6590.001.020 - WASHBROOK FLOWISE - EXTENDED SIDES FOR PRIVACY - WASHDOWN ACTION - FLUSHING RIM - 19 MM DIA.</p>	
<div><div><div></div><div><p>IBI GROUP 175 Galaxy Blvd, Unit 100 Toronto, ON M9W 0C9, Canada tel 416 679 1930 fax 416 675 4620 ibigroup.com</p></div></div><div><div></div><div><p>CITY OF TORONTO ACCESSIBILITY UPGRADES CITY OF TORONTO ACCESSIBILITY UPGRADES</p></div></div></div>		<p>DRAWING TITLE: WASHROOM FIXTURES & DRINKING FOUNTAIN</p>		<p>Project No: 9119- 19- 0162 / IBI 122260</p> <p>Date: 2022-11-01</p> <p>Issue: ISSUED FOR TENDER</p>	
<div><div><p>NO.</p><p>T03</p></div></div>					

ONLY WHEN ENTIRE KITCHEN MILLWORK IS TO BE REMOVED (UPPER AND LOWERS) ALL OTHER SCENARIOS, KITCHEN MILLWORK WILL MATCH EXISTING AESTHETIC



PERSPECTIVE: N.T.S



ELEVATION: N.T.S


PERSPECTIVE & ELEVATION VIEWS ARE REPRESENTATIVE ONLY - REFER TO BUILDING-SPECIFIC DRAWINGS




COUNTERTOP AND BACKSPLASH: Q-1
CAESARSTONE - QUARTZ
SUPERNATURAL COLLECTION
1111 VIVID WHITE



CABINETS: PLAM-2
PLASTIC LAMINATE
WILSONART NORTH
SEA D90



PAINT: PT-1
SHERWIN WILLIAMS SW
7004 SNOWBOUND
PAINT SHIELD EGGSHEL
SHEEN



UPPER CABINETS: PLAM-1
PLASTIC LAMINATE
WILSONART
ALABASTER D431



S1 FAUCET:
AMERICAN STANDARD NO.
7074100.00
SINK:
UCS6105P-1 SINGLE BOWL



S2 FAUCET:
AMERICAN STANDARD NO.
7074100.00
SINK:
FRANKE COMMERCIAL
UCD6405P



S3 FAUCET:
MOEN ALIGN WITH
MOTIONSENSE NO. 7565EC
SINK:
UCS6105P-1 SINGLE BOWL



S4 FAUCET:
MOEN ALIGN WITH
MOTIONSENSE NO. 7565EC
SINK:
FRANKE COMMERCIAL
UCD6405P



IBI GROUP
175 Galaxy Blvd, Unit 100
Toronto, ON M9W 0C9, Canada
tel 416 679 1930 fax 416 675 4620
ibigroup.com



CITY OF TORONTO
ACCESSIBILITY UPGRADES
CITY OF TORONTO
ACCESSIBILITY UPGRADES

DRAWING TITLE:

KITCHEN MATERIALS AND FIXTURES

Project No: 9119- 19- 0162 / IBI 122260

Date: 2022-11-01

Issue: ISSUED FOR TENDER

NO.

T04

RESERVED

RESERVED

RESERVED



IBI GROUP
175 Galaxy Blvd, Unit 100
Toronto, ON M9W 0C9, Canada
tel 416 679 1930 fax 416 675 4620
ibigroup.com



CITY OF TORONTO
ACCESSIBILITY UPGRADES
CITY OF TORONTO
ACCESSIBILITY UPGRADES

DRAWING TITLE:

RESERVED












Project No: 9119- 19- 0162 / IBI 122260


Date: 2022-11-01

Issue: ISSUED FOR TENDER

NO.

T05

 <p>TA - 1a (SURFACE MOUNTED) INTERIOR AND EXTERIOR TA - 1b (CAST IN PLACE) EXTERIOR TA - 1c (SURFACE MOUNTED FIRE RATED) INTERIOR</p> <p>POLYMER, COMPOSITE TACTILE INDICATORS</p> <ul style="list-style-type: none">• SURFACE APPLIED SUITABLE FOR INTERIOR APPLICATIONS• FIRE RATED TILES FOR INTERIOR APPLICATIONS HIGHER THAN 6 FLOORS• CAST IN PLACE SUITABLE FOR EXISTING	 <p>TA - 2a (SURFACE MOUNTED) INTERIOR AND EXTERIOR TA - 2b (CAST IN PLACE) EXTERIOR</p> <p>ENGINEERED POLYMER COMPOSITE TACTILE INDICATORS</p> <ul style="list-style-type: none">• EXTERIOR APPLICATIONS• FOR NEWLY CONSTRUCTED CURBS RAMPS, STAIRS, RAMPS, OR PLATFORM EDGES	 <p>TA - 3</p> <p>TRUNCATED DOMES WAYFINDING BARS</p> <p>RESILIENT POLYMER TACTILE INDICATORS</p> <ul style="list-style-type: none">• INTERIOR OR EXTERIOR APPLICATIONS• TRUNCATED DOME OR WAYFINDING BAR VARIANTS.• FOR SKATE RINK EDGES OR USE WITH VCT FLOORING	 <p>TA - 4</p> <p>TRUNCATED DOMES WAYFINDING BARS</p> <p>PORCELAIN TACTILE INDICATORS</p> <ul style="list-style-type: none">• INTERIOR OR EXTERIOR APPLICATIONS• TRUNCATED DOME OR WAYFINDING BAR VARIANTS.• FOR USE WITH PORCELAIN TILE FLOORING	
 <p>TA - 5</p> <p>CAST IRON CAST IN PLACE TACTILE INDICATORS</p> <ul style="list-style-type: none">• EXTERIOR APPLICATION• HIGHLY DURABLE• FOR NEW CONSTRUCTION HIGH TRAFFIC AREAS	 <p>TA - 6</p> <p>INDIVIDUAL STAINLESS STEEL PLATE TACTILE INDICATORS</p> <ul style="list-style-type: none">• INTERIOR OR EXTERIOR APPLICATIONS• FOR HIGH PROFILE ARCHITECTURAL SPACES WHERE AESTHETICS ARE IMPORTANT	 <p>TA - 7</p> <p>TRUNCATED DOMES:</p> <ul style="list-style-type: none">• INDIVIDUAL STAINLESS STEEL TACTILE INDICATORS• INTERIOR OR EXTERIOR APPLICATIONS• CAN BE INSTALLED ON ALL SURFACES• FOR HIGH PROFILE ARCHITECTURAL SPACES WHERE AESTHETICS ARE IMPORTANT• TO BE USED ON NON-HERITAGE DESIGNATED STAIRS	 <p>TA - 8</p> <p>GUIDANCE BARS:</p> <ul style="list-style-type: none">• INDIVIDUAL STAINLESS STEEL, BRASS, BRONZE OR ALUMINUM CARBORUNDUM NON-SLIP OR LINEAR GROOVE PATTERN.• INTERIOR APPLICATIONS• CAN BE INSTALLED ON ALL SURFACES• FOR HIGH PROFILE ARCHITECTURAL SPACES WHERE AESTHETICS ARE IMPORTANT• TO BE USED ON NON-HERITAGE DESIGNATED STAIRS	 <p>TA - 9</p> <p>INDIVIDUAL ANODIZED STAINLESS STEEL PLATE TACTILE INDICATORS</p> <ul style="list-style-type: none">• INTERIOR OR EXTERIOR• RESISTANT TO HEAVY TRAFFIC ABUSE AND MAINTENANCE MACHINERY• APPLICATIONS FOR HIGH PROFILE ARCHITECTURAL SPACES WHERE AESTHETICS ARE IMPORTANT
<div><div></div><div>IBI GROUP 175 Galaxy Blvd, Unit 100 Toronto, ON M9W 0C9, Canada tel 416 679 1930 fax 416 675 4620 ibigroup.com</div></div> <div><div>CITY OF TORONTO ACCESSIBILITY UPGRADES CITY OF TORONTO ACCESSIBILITY UPGRADES</div></div>	DRAWING TITLE: TACTILE ATTENTION INDICATORS		Project No: 9119- 19- 0162 / IBI 122260 Date: 2022-11-01 Issue: ISSUED FOR TENDER	NO. T06



TA - 11 INTERIOR AND EXTERIOR TEXTURAL WARNING STRIP

- AFFIXED WITH ADHESIVE AND SCREWS
- SIZES: 50.8MM X 203MM
- REFER TO DRAWINGS FOR REQUIRED LENGTH AND WIDTH



TA - 12 EXTERIOR CAST IN PLACE CONTRAST AND TEXTURAL WARNING STRIP

- DESIGNED FOR INSTALLATION ON STEP EDGES WHEN CONCRETE IS POURED.
- INSTALLED IN WET-SET CONCRETE.
- SIZES: 50.8MM X 76.2MM WIDE
- REFER TO DRAWINGS FOR REQUIRED LENGTH AND WIDTH



TA - 16 INTERIOR AND EXTERIOR USE (ON EXISTING) ON SMOOTH SURFACES STAIR NOSING FOR: TILE, CONC, WOOD, CARPET, VINYL.

- ANODIZED ALUMINUM NOSE, INSTALLED WITH EITHER NON-SLIP STRIP OR WITH PHOTOLUMINESCENT CONTRAST STRIP.
- AVAILABLE IN 5 DIFFERENT PROFILES TO MATCH THE DESIGN OF THE STEP EDGE
- AFFLICTED WITH ADHESIVE OR ADHESIVE AND SCREWS
- SIZES: 70.1MM - 78.7MM WIDE
- REFER TO DRAWINGS FOR REQUIRED LENGTH AND WIDTH



TA - 17 INTERIOR USE ON NEW TILED SURFACES. STAIR NOSING.

- ALUMINUM NOSE SPECIFICALLY DESIGNED FOR INSTALLATION ON TILED STAIRS.
- 3.2MM TILED STAIRS OR 2.54MM TILED STAIRS.
- REFER TO DRAWINGS FOR REQUIRED LENGTH AND WIDTH



TA - 18 INTERIOR USE ON NEW CARPETED FLOORING. STAIR NOSING.

- ANODIZED ALUMINUM NOSE, SPECIFICALLY DESIGNED FOR CARPETED STAIRS, INSTALLED WITH EITHER NON-SLIP STRIP OR WITH PHOTOLUMINESCENCE CONTRAST STRIP
- INSTALLED WITH SCREWS
- SIZES: 66MM - 89MM
- REFER TO DRAWINGS FOR REQUIRED LENGTH AND WIDTH



TA - 19 EXTERIOR USE ON POURED CONCRETE. STAIR NOSING.

- HEAT TREATED EXTRUDED ALUMINUM ALLOY 6063-T-6, FILLED WITH A MIXTURE OF VIRGIN ALUMINUM OXIDE AND SILICON CARBIDE ABRASIVE GRANULES IN AN EPOXY BINDER.
- FULL LENGTH, INTEGRALLY EXTRUDED 5/8" ANCHOR.
- SIZES: 79.4MM X 25.4MM
- REFER TO DRAWINGS FOR REQUIRED LENGTH AND WIDTH
- TO BE USED ON NON-HERITAGE DESIGNATED STAIRS



TA - 20 INDOOR AND OUTDOOR USE ON NEW POURED CONCRETE STAIR NOSING.

- INSTALL INTO WET CONCRETE. USED ON CONCRETE STAIRS, CONCRETE-FILLED STEEL PAN STAIRS, AND PRE-CAST CONCRETE STAIRS.
- AVAILABLE IN CUT TO LENGTH SIZES. (TOLERANCE +OR- 1/8")
- STANDARD LENGTHS ARE 8FT AND 10FT.
- INSERTS ATTACHED OR UNATTACHED – INSERTS UNATTACHED CAN BE INSTALLED LATER TO ENSURE THE PRODUCT IS CLEAN AND HAS NOT BEEN DAMAGED DURING CONSTRUCTION. INSERTS ARE INSTALLED WITH A PREMIUM POLYURETHANE ADHESIVE.
- A CLEAR PROTECTIVE TAPE WRAPS AROUND THE PRODUCT TO KEEP THE PRODUCT CLEAN DURING INSTALLATION. TO REMOVE, CUT THE TAPE ALONG THE EDGES AND PEEL AWAY.



IBI GROUP
175 Galaxy Blvd, Unit 100
Toronto, ON M9W 0C9, Canada
tel 416 679 1930 fax 416 675 4620
ibigroup.com



CITY OF TORONTO
ACCESSIBILITY UPGRADES
CITY OF TORONTO
ACCESSIBILITY UPGRADES

DRAWING TITLE:
TEXTURAL & COLOUR CONTRAST
WARNING STRIP AND NOSING

Project No: 9119- 19- 0162 / IBI 122260

Date: 2022-11-01

Issue: ISSUED FOR TENDER

NO.

T07


TH-1a

SMOOTH 6" WIDE THRESHOLD WITH ANTI-SLIP COATING



TH-2a

EXTERIOR APPLICATIONS - THERMALLY BROKEN METAL THRESHOLD
ANY EXISTING FLOORING MATERIAL TO ANY EXISTING FLOORING MATERIAL



TH-3a

METAL THRESHOLD
ANY EXISTING FLOORING MATERIAL TO ANY EXISTING FLOORING MATERIAL



TH-4a

ANODIZED ALUMINUM TRANSITION STRIP
BETWEEN NEW AND EXISTING FLOOR



TH-5a

SATIN ANODIZED ALUMINUM TRANSITION STRIP
FOR NEW FLOORING ON BOTH SIDE VARIES HEIGHTS (TILE TO ANY FLOOR SURFACE)

