



REVISIONS			
no.	remarks	date	by
01	Addendum	01 May 24	fh

2600 skymark avenue building 8, suite 101
mississauga, ontario L4W 5B2
☎ 416.621.7745
design@comileyvanbrussel.com


project

PEEL REGIONAL POLICE
7150 Mississauga Road
Mississauga ON L5N 8M5
Gr. 2nd & 3rd Floors

title
THIRD FLOOR
FLOOR FINISHES PLAN- ALT PRICE



3RD FLOOR KEY PLAN



1 FLOOR FINISHES PLAN - THIRD FLOOR - ALTERNATIVE PRICE
D7.1A SCALE: 1/8" = 1'-0"

FLOOR FINISHES PLAN LEGEND

<p>CARPET FLOOR - 1 NEW CARPET MANUFACTURER: MORNIK PATTERN: WILD PERS COLLECTION CIRCUS CLUSTER COLOR: #1727 VERY CURIOUS INSTALLATION METHOD: GUESS DOWN BROOK ASHAR</p> <p>CARPET - 1 WILD PERS COLLECTION CIRCUS CLUSTER COLOR: #1727 VERY CURIOUS INSTALLATION METHOD: GUESS DOWN BROOK ASHAR</p> <p>CARPET - 1 WILD PERS COLLECTION CIRCUS CLUSTER COLOR: #1727 VERY CURIOUS INSTALLATION METHOD: GUESS DOWN BROOK ASHAR</p>	<p>LVT 1</p>	<p>LVT STRIP FLOORING - 1 NEW LVT MANUFACTURER: MORNIK SERIES/PATTERN: BASE & LOGO COLLECTION PATTERN OF THE C1916 COLOR: #855 SILVER LINING INSTALLATION METHOD: GUESS DOWN BROOK ASHAR BASE #2 - 4 1/2" VINYL BASE COLOR: 100 LUGA</p>	<p>TR 1</p>	<p>NEW TRANSITION STRIP TB-1 - TO MATCH EXISTING APPLICATION: CARPET TO LVT</p>
<p>CARPET FLOOR - 2 NEW CARPET MANUFACTURER: MORNIK PATTERN: WILD PERS COLLECTION WANDERING TROOP COLOR: #1727 A VERY CURIOUS INSTALLATION METHOD: GUESS DOWN BROOK ASHAR</p> <p>CARPET - 2 WILD PERS COLLECTION WANDERING TROOP COLOR: #1727 A VERY CURIOUS INSTALLATION METHOD: GUESS DOWN BROOK ASHAR</p> <p>CARPET - 2 WILD PERS COLLECTION WANDERING TROOP COLOR: #1727 A VERY CURIOUS INSTALLATION METHOD: GUESS DOWN BROOK ASHAR</p>	<p>LVT 2</p>	<p>LVT STRIP FLOORING - 2 NEW LVT MANUFACTURER: MORNIK SERIES/PATTERN: BASE & LOGO COLLECTION PATTERN OF THE C1916 COLOR: #855 WISPIER INSTALLATION METHOD: GUESS DOWN BROOK ASHAR BASE #2 - 4 1/2" VINYL STRIP GUT VINYL BASE ANNOI COLOR: 100</p>	<p>TR 2</p>	<p>NEW TRANSITION STRIP TB-2 - TO MATCH EXISTING APPLICATION: CARPET TO GRANITE TILE</p>
<p>CARPET FLOOR - 3 NEW CARPET MANUFACTURER: MANNINGTON COMMERCIAL PATTERN: NASHVILLE - 18"X24" CARPET PLANK COLOR: #17383 LAUREL HURST INSTALLATION METHOD: GUESS DOWN BROOK ASHAR</p> <p>CARPET - 3 NASHVILLE - 18"X24" CARPET PLANK COLOR: #17383 LAUREL HURST INSTALLATION METHOD: GUESS DOWN BROOK ASHAR</p> <p>CARPET - 3 NASHVILLE - 18"X24" CARPET PLANK COLOR: #17383 LAUREL HURST INSTALLATION METHOD: GUESS DOWN BROOK ASHAR</p>	<p>LVT 3</p>	<p>LVT STRIP FLOORING - 3 NEW LVT TO MATCH EXISTING MANUFACTURER: MANNINGTON COMMERCIAL SERIES/PATTERN: SYDRA - 18"X24" CARPET PLANK COLOR: PALE ASPH #526218 INSTALLATION METHOD: GUESS DOWN BROOK ASHAR BASE #2 - 4 1/2" VINYL BASE TO MATCH EXISTING</p>	<p>TR 3</p>	<p>NEW TRANSITION STRIP TB-3 APPLICATION: FINISHED CARPET TO CARPET MANUFACTURER: SCOTCH ALUMINUM SPECIFICATION: REMU FINISH: ANODIZED ALUMINUM</p>
<p>GRANITE FLOOR - 1 BASE - 1 12"X18" GRANITE BASE, TO MATCH EXISTING. REFER TO NOTE F-1</p>	<p>LVT 4</p>	<p>LVT STRIP FLOORING - 4 NEW LVT TO MATCH EXISTING MANUFACTURER: MANNINGTON COMMERCIAL SERIES/PATTERN: ANTIOCH - 4"X10" REVISED EDGE PROFILE COLOR: CHERO # A00700 INSTALLATION METHOD: GUESS DOWN BROOK ASHAR BASE #2 - 4 1/2" VINYL BASE</p>	<p>TR 4</p>	<p>DENOTES DIRECTION OF FLOORING</p>

KEY NOTES	
FF 1	FLOORING CONTRACTOR TO REMOVE EXISTING 4" GRANITE BASE AND REINSTALL TO SUIT NEW DOOR LAYOUT. IF GRANITE CANNOT BE REMOVED, NEW 1"X4" BLACK GRANITE IS TO BE INSTALLED FROM PERIMETER WINDOW TO COLUMN.
FF 2	SUPPLY AND INSTALL CARPET/VINYL BASE TO BE GLUED TO EXISTING MILLWORK AND PLATE.
FF 3	EXISTING CONCRETE FLOORING TO REMAIN
FF 4	EXISTING CARPET/VINYL TO REMAIN. CONTRACTOR TO SUPPLY AND INSTALL NEW CARPET/VINYL BASE TO MATCH EXISTING WHERE DEMO OCCURS AND AT NEW PARTITIONS
FF 5	WHERE DEMOLITION OCCURS, CONTRACTOR TO REMOVE WALL BASE AND REPLACE WITH ONE CONTINUOUS WALL BASE. 5" PIECE INSTALLED AT WALL SCAR IS NOT ACCEPTABLE.
FF 6	REFER TO RENDERING
FF 7	TILE FLOORING TO REMAIN AS IS
FF 8	LOCATION OF SECURE HOARDED AREA. REFER TO KEY NOTE P 5
FF 9	CARPET INSERT IN LIT FLOORING. ENSURE SMOOTH TRANSITION FROM LIT TO CARPET TO AVOID TRIPPING HAZARD

FLOOR FINISHES PLAN : NOTES

1. THIS DRAWING MUST BE REVIEWED & COORDINATED WITH ALL OTHER DRAWINGS OF ALL CONSULTANTS INCLUDING BUT NOT LIMITED TO MECHANICAL AND ELECTRICAL ENGINEERING DRAWINGS AND SPECIFICATIONS. EXTRAS FOR APPLIED WORK THAT WAS COVERED ON ANY OF THE DRAWINGS ETC. NOT COVERED IN THIS DRAWING WILL NOT BE CONSIDERED.
2. ALL FINISHES ARE TO BE HANDLED AND USED IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS AND BASE BUILDING TANK CONSTRUCTION MANUAL.
3. **ALL FLOORING TO BE CLEANED, SEALED AND PROPERLY FINISHED ACCORDING TO MANUFACTURERS SPECIFICATIONS PRIOR TO CLIENT MOVE IN.**
4. ALL FLOOR AND BASE ADHESIVE MUST NOT EXCEED THE FOLLOWING REQUIREMENTS:
 - ADHESIVES, SEALANT AND SEALANT PRIMER: SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD) RULE # 1108 REQUIREMENTS IN EFFECT JANUARY 1, 2003 AND RULE AMENDMENT DATED OCTOBER 1, 2003.
 - AEROSOL ADHESIVES: GREEN SEAL STANDARD GS-36 REQUIREMENTS IN EFFECT OCTOBER 19, 2003. CONTRACTOR MUST SUBMIT PRODUCT DATA SHEETS VERIFYING ADHERENCE TO THESE STANDARDS FOR DESIGNER SIGN OFF.
5. SUB-FLOOR TO BE FREE OF ALL DEBRIS AND GUE PRIOR TO SUB-FLOOR INSTALLATION.
6. LAYOUT FLOORING PATTERNS FOR REVIEW BY DESIGNER PRIOR TO INSTALLATION OF FLOORING. PROVIDE 24 HOURS NOTICE TO DESIGNER.
7. TRANSITIONS FROM ONE FLOORING MATERIAL TO THE NEXT TO BE MADE LEVEL. FEATHER FLOOR WITH APPROPRIATE FLOOR LEVELER. AS REQUIRED TO MAKE ADJACENT FLOORING MATERIALS FLUSH.
8. CONTRACTOR TO PROVIDE FLOORING TAPE TO ALL CORNERS OF TILES OR ADHESIVE PER MANUFACTURERS RECOMMENDATION FOR INSTALLATION.
9. CONTRACTOR TO ALLOW FOR SELF LEVELING TO CONCRETE FLOORS, AS AT ALL NEW DOORWAYS.
10. **EXISTING FLOORING IS TO BE PATCHED WHERE DEMOLITION OCCURS. CONTRACTOR TO LIFT EXISTING CARPET, TILES AND SEAL AS PER NEW LAYOUT. DISPOSE OF BASE PRIOR TO LAY.**
11. CONTRACTOR TO ALLOW FOR 2% OF EXISTING FLOOR CARPET TILES NOT WITHIN SCOPE TO BE DEMOLISHED (STAINED OR HEAVILY WORN TILES). CONTRACTOR WILL REPLACE WITH TILES SALVAGE OR REPLACEMENT. REPLACE WITH GOOD CONCRETE TILES ONLY.