

**CITY OF VAUGHAN
FIRE STATION 7-12**

9511 WESTON ROAD, VAUGHAN

CLIN




ARCHITECT
THOMASBROWNARCHITECTS
197 SPADINA AVENUE, SUITE 500 | TORONTO ONTARIO | M5T 2C8

PROFESSIONAL SEAL

DWG TITLE

DOOR FINISH SCHEDULE

ORIENTATION



DATE 2021-11-24

SCALE
As indicated

DWG STATUS : TENDER

PROJECT No. _____

2104

24 DRAWING No.


A13.6

24 DRAWING No.


A13.6

REVISIONS


26




1 DOOR LEGEND AND FRAME TYPES



FRAME TYPES



HM FRAME DEFINITIONS



NOTES:

- NOTES:
1. SHOP DRAWING REQUIRED PRIOR TO FABRICATION. SHOP DRAWINGS SHALL REFERENCE DOOR TYPE ELEVATIONS AS SHOWN
 2. DOOR AND FRAME MATERIAL - REFER TO SCHEDULE.
 3. ALL DOORS AND FRAMES IN RATED ASSEMBLIES SHALL BE PROPERLY LABELLED
 4. GATES IN EXTERIOR DOORS SHALL BE EXPOSED EDGES OF DOOR AND FRAMES
 5. UNDERCUT DOORS WHERE INDICATED ON DRAWINGS
 6. REFER TO MECHANICAL DRAWINGS FOR LOUVER SIZES IN TYPE 'L' DOORS
 7. GATES IN EXTERIOR DOORS SHALL BE SEPARATELY DETAILLED IF BROKEN
 8. ALL EXTERIOR DOOR FRAMES SHALL BE FILLED WITH CLOSED CELL FOAM INSULATION (JAMBS AND HEADS)
 9. ALL EXTERIOR DOORS SHALL BE COMPLETELY WEATHERSTRIPPED
 10. ALL EXTERIOR DOORS SHALL HAVE A PREFABRICATED ALUMINUM THRESHOLD
 11. CALCUL FLOOR TO FLOOR AT EXPOSED CONCRETE FLOOR FINISHES
 12. ALL DOORS SHALL BE COMPLETED TO FLOOR FINISH

 FIRE DOOR INSTALLATION DETAILS