1. GENERAL

    1. GENERAL REQUIREMENTS

        1. Section 01 01 00 - General Requirements is a part of this Section and shall apply as if repeated here.

2. APPOINTMENT AND PAYMENT OF INSPECTION COMPANIES

    1. Inspection and Testing Companies for various trades will be appointed by the Consultant where specifically stated or required or as determined during the work.

    2. The cost of inspection and testing will be paid by the Owner, except where tests or inspections reveal work not in accordance with the Contract, the Contractor shall bear the cost of such tests and additional tests as the Architect requires to verify the acceptability of corrected work.

3. RESPONSIBILITIES

    1. The Architect will supply drawings and specifications as required for the use of the respective inspection and testing authorities and advise the Contractor of the Company appointed for the respective work.

    2. The Contractor shall advise the Architect and the respective Inspection and Testing authority not less than 5 working days prior to the commencement of any work to be inspected or tested and ensure that proper facilities and co-operation is provided and that no work is carried out without the required inspection and testing.

    3. Proper storage shall be provided for storing concrete specimens at the job site at the required temperature and free from vibration or injury.

End of Section 01 41 10