1. See Individual Specifications Sections for full listing of inspections and approvals.

2. Consultant's approvals required:

    1. All Consultant's approval as required before interfering with existing services and apparatus. One week notice to be given; Section 01 01 00.

    2. Consultant's approval before installing flooring; Section 01 01 00.

    3. Consultant's approval of work schedule (Progress Schedule); Section 01 31 10.

    4. Consultant's approval of construction signs and locations; Section 01 11 00.

    5. Consultant's approval of temporary fence and layout; Section 01 11 00.

    6. All Consultant's approval as required for substitutions; Section 01 50 00.

    7. All Consultant's approval as required of cast-in-place concrete materials, sandblasting, tint, admixtures and tests; Section 03 30 00

    8. Consultant's approval of caulking joint samples; Section 07 90 00

    9. Consultant's approval of sealant samples; Section 07 90 00.

3. Notify Consultant:

    1. Notify Consultant and Inspection and Testing Company 7 days in advance before commencing roofing; Section 07 62 00.

    2. Notify Consultant for Deficiency Inspection upon agreed Substantial Completion.

    3. Notify Consultant AND Owner for One-Year Inspection.

4. Submit samples for approval.

End of Section 01 30 10