

SUNNYBROOK HEALTH SCIENCES CENTRE SHSC OR3 & OR4 LEAD INSTALLATION

RFT NO. CW22886

ADDENDUM 03

Issued: March 24, 2025

1.0 GENERAL

This Addendum is issued in accordance with Section 4 – Addenda and amends the original Request For Tender (RFT) and associated documents as set out below. The revisions shall become part of the RFT documents and change the original RFT documents only in the manner and extent stated.

This Addendum shall be attached to the above noted **RFT** and shall form an integral part of the **RFT**. The contents of this Addendum shall be brought to the attention of all concerned.

2.0 DOCUMENTATION ISSUED UNDER THIS ADDENDUM:

2.1 The Closing date has been extended until **March 31, 2025, at 2:00 PM (EST)**.

2.2 OR 3-4 Addendum 03 20250320[2] (1 page)

3.0 QUESTIONS AND ANSWERS

3.1 The following questions pertaining to the **Request for Tender** have been received from the Respondents and the following answers are being provided to all Respondents.

None

End of Addendum No. 03

The bid requirements, contract requirements, specifications, schedules and drawings for

**Sunnybrook Health Sciences Centre
OR 3 & 4 Lead Installation**

are amended as follows:

This Addendum is issued prior to Bid due date to revise the Bid/Contract Documents and as such is part of the Contract Documents; value of all items shall be included in Bid. After acceptance of Bid, claims for costs will not be considered by reason of failure by Bidder to have read Addenda.

DRAWINGS

1.1 REVISED DRAWINGS

- .1 The following drawings are revised by reference, but not re-issued:
 - .1 Drawing A01-05R1 Door & Frame schedule, screen schedule, partition legend & details.
 - .1 Door and Frame Schedule, delete door 234-C from schedule.
 - .2 Drawing A20-02R1 Level 2 overall construction floor plan
 - .1 New Door 234-C in OR4 is not required. Remove existing door as per demolition plan, infill opening with steel studs and GB to match existing. Patch, repair and paint wall from storage room side, install new wall protection in OR side. Patch flooring to match existing on storage room side.

CLARIFICATIONS

1.2 CLARIFICATIONS

- .1 Screen, Cameras, Black Box and related equipment will be removed by the Equipment Vendor engaged by the Owner. Contractor shall coordinate the Work with Equipment Vendor and shall be responsible for removing and reinstalling of existing mounting hardware.
- .2 In the each OR the three workstation computers, printers and scanners will be removed by SHSC, but all brackets, whiteboards, and hooks will remain for the contractor to identify locations, remove and replace after walls are rebuilt. For all wall perforations, brackets, and hooks, protection will be required for the lead shielding to maintain integrity.
- .3 All equipment on wheels or portable, will be removed by SHSC.

End of Addendum No.3

NORR
175 Bloor Street East
North Tower, 15th floor,
Toronto, Ontario
M4W 3R8