

ROOM FINISH SCHEDULE							
ROOM NAME	CEILING HEIGHT	FLOOR	WALLS				CEILING
			NORTH	EAST	SOUTH	WEST	
Lobby	7.5		PT6 / PT2		PT2		
Reception	7.5		PT6	PT6 / PT2			
Meeting Room	3.6		PT1 / PT2	PT1	PT1	PT1	PT7
Family Changeroom	3.3		PT1	PT1	PT1	PT1	PT7
Men's Changeroom	3.3		PT1	PT1	PT1	PT1	PT7
Women's Changeroom	3.3		PT1	PT1	PT1	PT1	PT7
Corridor 2	3.3		PT1 / PT2	PT1 / PT2 / PT3	PT1	PT1	PT7
Multi-purpose Room	3.3		PT1		PT1 / PT2	PT1 / PT2	PT7
Pool	6.9	PT4 / PT8	PT1 / PT2	PT1	PT1	PT1 / PT2	PT7

ROOM FINISH SCHEDULE GENERAL NOTES (TYPICAL):

- VERIFY THE CONDITION OF ALL SURFACES PRIOR TO PAINTING.
- PATCH AND MAKE GOOD ALL EXISTING SURFACES AS REQUIRED TO ACHIEVE A UNIFORM AND CONTINUOUS APPEARANCE.
- PATCH AND MAKE GOOD ALL EXISTING CEILINGS TO ACHIEVE A UNIFORM AND CONTINUOUS APPEARANCE.
- ENSURE ALL PAINTED SURFACES ARE FREE OF DUST AND DEBRIS BEFORE PAINTING.
- MASK AND COVER ALL FIXTURES, SWITCHES, AND OUTLETS BEFORE PAINTING.
- USE DROP CLOTHS AND PROTECTIVE SHEETING TO COVER FLOORS, FURNITURE, EQUIPMENT AND ETC.
- PROTECT ALL ADJACENT SURFACES FROM PAINT SPLATTERS AND DRIPS.
- USE ONLY APPROVED PAINT MATERIALS AND COLORS AS SPECIFIED.
- PAINT ALL WALL AND FRAME SURFACES.
- PAINT BOTH SIDES OF ALL DOOR AND WINDOW FRAME SURFACES.
- PAINT ALL PAINTABLE AND PREVIOUSLY PAINTED DOORS AND FRAMES.
- PAINT ALL BULKHEADS, HORIZONTAL, AND VERTICAL SURFACES.
- PAINT ALL PREVIOUSLY PAINTED SURFACES TO MAINTAIN CONSISTENCY AND COVERAGE.
- ENSURE ALL PAINT LAYERS ARE EVEN AND CONSISTENT IN COLOR.
- ALLOW SUFFICIENT DRYING TIME BETWEEN COATS AS PER MANUFACTURER'S INSTRUCTIONS.
- DO NOT PAINT ANY FIRE ALARMS OR LIFE SAFETY DEVICES.
- DO NOT PAINT ON NATURAL WOOD TEXTURE AREAS.
- DO NOT PAINT ANY SCREWED-ON DEVICES.
- DO NOT PAINT ANY WALL TILES UNLESS OTHERWISE NOTED.
- DO NOT PAINT MILLWORK UNLESS OTHERWISE NOTED.
- DO NOT PAINT ON OUTLETS AND COVER AD BUTTONS.
- DO NOT PAINT ON WATER FOUNTAINS.
- DO NOT PAINT ON WOOD TEXTURE RAILINGS, LIGHTING COVERS, ETC.
- REMOVE, SALVAGE, STORE, AND REINSTALL ALL SIGNS AFTER PAINTING.
- REMOVE, SALVAGE, STORE, AND REINSTALL ALL WALL-MOUNTED BULLETIN BOARDS AFTER PAINTING.
- REMOVE, SALVAGE, STORE, AND REINSTALL ALL WALL-MOUNTED ACCESSORIES IN WASHROOMS AND OTHER ROOMS AFTER PAINTING.
- REMOVE, SALVAGE, STORE, AND REINSTALL ALL WALL-MOUNTED ITEMS SUCH AS SIGNAGE THAT ARE LESS THAN 12 FT X 12 FT AFTER PAINTING.
- PROVIDE PROPER VENTILATION IN AREAS BEING PAINTED TO ENSURE SAFETY.
- ALL PAINTING WORK MUST COMPLY WITH LOCAL BUILDING CODES AND STANDARDS.
- MAINTAIN A CLEAN AND ORGANIZED WORK AREA THROUGHOUT THE PAINTING PROCESS.
- CLEAN AND DISPOSE OF ALL PAINTING MATERIALS AND WASTE ACCORDING TO ENVIRONMENTAL REGULATIONS.
- PROVIDE TOUCH-UP PAINT FOR FUTURE USE BY THE OWNER.
- DOCUMENT ANY CHANGES OR DEVIATIONS FROM THE ORIGINAL PAINTING PLAN.
- REMOVE ALL PAINTING EQUIPMENT AND MATERIALS FROM THE SITE UPON COMPLETION.
- CONDUCT A FINAL INSPECTION WITH THE PROJECT MANAGER TO ENSURE ALL PAINTING WORK MEETS QUALITY STANDARDS AS PER THE SPECIFICATIONS.
- ENSURE ALL PAINTING WORK IS PERFORMED BY QUALIFIED AND EXPERIENCED PERSONNEL.
- REMOVE ANY LOOSE OR PEELING PAINT FROM WALLS, FLOORS, CEILINGS, AND STEPS. PATCH AND REPAIR ANY DENTS, CRACKS, OR IMPERFECTIONS IN WALLS. PRIME AND PAINT WALLS, CEILINGS, AND SURFACES.
- KEEP CORRIDORS AND COMMON AREAS CLEAR. THIS BUILDING WILL REMAIN OCCUPIED AND FULLY OPERATIONAL FOR THE DURATION OF THIS PROJECT.
- THE CONTRACTOR IS TO INCLUDE THE REMOVAL AND REINSTALLATION OF WALL-MOUNTED ITEMS AS REQUIRED TO COMPLETE THIS FULL SCOPE OF WORK. THE CONTRACTOR MUST CONFIRM REQUIREMENTS DURING SITE VISITS.
- REMOVE EXISTING ADHESIVE, CAULKING, AND PAINT LINES FROM THE BASE OF EXISTING WALLS FOR INSTALLATION OF NEW OR REINSTALLED RUBBER BASE MATERIALS. SKIM COAT AS REQUIRED.
- MECHANICAL AND ELECTRICAL DEVICES SUCH AS LIGHTING ARE NOT INDICATED ON THE DRAWINGS. CONTRACTOR SHALL CUT-IN AROUND ALL EXISTING LIGHT FIXTURES IN A MANNER SO THAT PAINT LINES ARE NOT VISIBLE.
- ALL WORK SHALL BE PERFORMED DURING THE DAY TIME WITH TIME TO ALLOW SURFACES TO DRY PRIOR TO DAILY OCCUPANCY.
- THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING AND MANAGING THE MOVING OF FURNITURE AND EQUIPMENT, INCLUDING GYM EXERCISE EQUIPMENT, FOLLOWING THE COMPLETION OF PAINTING. THIS INCLUDES SAFELY REMOVING, STORING AND REINSTATING THE EQUIPMENT TO ITS ORIGINAL CONDITION. THE CONTRACTOR MUST ENSURE THAT ALL EQUIPMENT IS PROPERLY RESTORED AND SECURELY REASSEMBLED TO ENSURE THE SAFETY OF USERS. ADDITIONALLY, A THIRD-PARTY SAFETY INSPECTION IS REQUIRED.
- PAINT ALL EXPOSED STEEL BRACKETS.
- REMOVE, DISCONNECT, STORE, AND REINSTALL ALL ELECTRICAL DEVICES SUCH AS TV, POS SYSTEM, COMPUTERS, PHOTOCOPIERS, ETC.
- CONTRACTOR TO REMOVE EXISTING SEALANTS AND PROVIDE NEW SEALANTS AT ALL MATERIAL JUNCTIONS. ENSURE THAT ALL JUNCTIONS ARE PROPERLY CLEANED AND PREPARED BEFORE APPLYING NEW SEALANTS. VERIFY
- CONTRACTOR SHALL PAINT ALL EXPOSED MECHANICAL DUCTWORK TO MATCH THE ADJACENT SURFACES, UNLESS OTHERWISE NOTED ON THE DRAWING OR ROOM FINISHING SCHEDULE.
- CONTRACTOR SHALL PAINT ALL PREVIOUSLY PAINTED RADIATORS TO MATCH THE ADJACENT SURFACES, UNLESS OTHERWISE NOTED ON THE DRAWING OR ROOM FINISHING SCHEDULE.
- DO NOT PAINT OVER FIRE-RATED LABELS ON DOORS AND DOOR FRAMES, REGARDLESS OF WHETHER THEY HAVE BEEN PREVIOUSLY PAINTED.

COLOUR FINISH SCHEDULE

	Colour	Sheen	Location	Sample
PT1	Benjamin Moore CSP-250 "Dulce de Leche"	Eggshell / Semi-gloss	Interior Walls	PT1
PT2	Sherwin Williams SW-7017 "Dorian Grey"	Semi-gloss	Metal Hollow Frames All Door (Both Sides)	PT2
PT3	Benjamin Moore CSP-250 "Dulce de Leche"	Semi-gloss	Radiators	PT3
PT4	Traffic Yellow	Semi-gloss	All Stair Nosing	PT4
PT5	Sherwin Williams SW-9185 "Marea Baja"	Semi-gloss	Lockers	PT5
PT6	Benjamin Moore AC - 28 "Heirloom Quilt"	Eggshell	Interior Walls	PT6
PT7	White	Eggshell / Semi-gloss	Interior Ceiling: Eggshell in Common Areas Semi-gloss in Wet Areas Metal Deck & Beams Ductwork	PT7
PT8	Sherwin Williams SW-7017 "Dorian Grey"	Semi-gloss	Stands in Pool Area	PT8

CHERIE NG
ARCHITECT INC.
www.cherienng.com
t. 416.898.1979

general notes :

1. These Contract Documents are the property of the Architect. The Architect bears no responsibility for the misinterpretations of these documents by the Contractor. Upon written application the Architect will provide written / graphic clarification or supplemental information regarding the intent of the Contract Documents. The Architect will review Shop Drawings submitted by the Contractor for design conformance only.

2. Drawings are not to be scaled for construction. Contractor to verify all existing conditions and dimensions required to perform the Work and report any discrepancies with the Contract Documents to the Architect before commencing work.

3. Positions of exposed or finished mechanical or electrical devices, fittings, and fixtures are indicated on the Architectural drawings. The locations shown on the Architectural drawings govern over the Mechanical and Electrical drawings. Those items not clearly located will be located as per directed by the Architect.

LEGEND:

OUTSIDE OF SCOPE


DOOR: DO NOT PAINT

PAINT DOOR & FRAMES BOTH SIDES


- PT1 Colour #1
- PT2 Colour #2
- PT3 Colour #3
- PT4 Colour #4
- PT6 Colour #6
- PT7 Colour #7
- PT8 Colour #8

SEPARATE PRICE:

- PT1 Colour #1
- PT5 Colour #5



ISSUED FOR ADDENDUM NO.1	08 APRIL 2025
ISSUED FOR TENDER	01 NOVEMBER 2024
ISSUED FOR TENDER	29 JULY 2024
revision	date



ALDERWOOD CENTRE
PAINTING ENHANCEMENT
Address: 2 ORIANNA DR, TORONTO
FLOOR PLAN /
SCHEDULES

project no.: 2419
scale: 1/200
date: APRIL 2025

drawing no.:

A2.1