

PART 1 – GENERAL

1.1 GENERAL INSTRUCTIONS

- .1 Read and be governed by conditions of the *Contract Documents*, including Sections of Division 01.

1.2 SECTION INCLUDES

- .1 1.1 General Instructions
- .2 1.2 Section Includes
- .3 1.3 Summary
- .4 1.4 Submittals
- .5 2.1 Materials
- .6 3.1 Laying

1.3 SUMMARY

- .1 Clay brick.

1.4 SUBMITTALS

- .1 Submit required submittals in accordance with Section 01 33 00 – Submittal Procedures and Section 04 05 00 – Masonry Procedures.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Manufacture: Manufacture total required brick in one continuous batch, for maximum colour and texture uniformity.
- .2 Clay brick:
 - .1 Exterior kiln fired clay brick veneer: in accordance with CAN/CSA A82.1-M87.
 - .1 Grade SW.
 - .2 Type: FBX.
 - .2 Size: Modular: 57 mm x 92 mm x 194 mm (2-1/4" x 3-5/8" x 7-5/8").
 - .3 Acceptable *Product*:
 - .1 'Endicott Manganese Ironspot Velour' complete with natural mortar, as distributed by Thames Valley
 - .2 'Glen-Gery Blue Ironspot Velour' complete with natural mortar, as distributed by Brampton Brick
 - .3 'Glen-Gery Ebonite Velour' complete with natural mortar, as distributed by Brampton Brick
 - .4 Or *Equivalent*.

PART 3 - EXECUTION

3.1 LAYING

- .1 Lay masonry in accordance with good practice, CAN/CSA A371-04 and as accepted in mock-up sample wall and as specified in Section 04 05 00 – Masonry Procedures.
- .2 Review locations of coursing alignment and layout with the *Consultant*, and seek approval, prior to commencement of the work of this Section.

END OF SECTION