

Slab thickness was observed to range from 5"-7" with wire mesh reinforcements.

Majority of conduit run was observed in a trench, with multiple services clustered at various depths. Given that some services were as high as 5" (tight under slab). I would treat all markings along main trench as effectively embedded.

All markings reflects services that were either, visible on GPR data within 18" depth, or actively toned and located using induction clamping.

Plumbing at depth deeper then 18" not reflected in markings.

- Measurement
- Electrical
- Plumbing
- D# Depth in inches from top of slab

1F428A
Mechanical & Electrical

