

FINAL

Designated Substances Survey Report

Forensic Identification Unit –
Building A and Radio & Electronic
Services – Building B
2050 Jane Street, Toronto, ON

Prepared for:

The City of Toronto

Facilities Management
55 John Street, 2nd Floor
Toronto ON

Attention: Sara Reid
Environmental Project Manager

November 25, 2015

Pinchin File: 103037



Designated Substances Survey Report

Forensic Identification Unit – Building A and Radio & Electronic Services – Building B
2050 Jane Street, Toronto, ON
The City of Toronto

November 25, 2015

Pinchin File: 103037

FINAL

Issued to: The City of Toronto
Contact: Sara Reid
Environmental Project Manager
Issued on: November 25, 2015
Pinchin file: 103037
Issuing Office: 50 Wellington Street East, Suite
200, Toronto, ON M5E 1C8
Primary Contact: Juliette McIntyre

Reviewer: Juliette McIntyre
Senior Project Manager
jmcintyre@pinchin.com

Reviewer: Mark Stroombergen, C.E.T.
Director, GTA - Hazardous Materials
mstroombergen@pinchin.com



Designated Substances Survey Report

Forensic Identification Unit – Building A and Radio & Electronic Services – Building B
2050 Jane Street, Toronto, ON
The City of Toronto

November 25, 2015

Pinchin File: 103037

FINAL

EXECUTIVE SUMMARY

The City of Toronto (Client) retained Pinchin Ltd. (Pinchin) to conduct a Designated Substance survey of Forensic Identification Unit (Building A) and Radio & Electronic Services (Building B) located at 2050 Jane Street, Toronto, ON. The survey was performed on May 13, 2015.

The objective of the survey was to document the locations of specified Designated Substances, polychlorinated biphenyls (PCBs) and mould (referred collectively as hazardous building materials), evaluate their condition, and develop corrective action plans as required for the purposes of long term management. The results of this survey are not intended for construction, renovation, demolition or project tendering purposes.

The survey area consisted of the entire area of both buildings. The building was occupied at the time of the survey.

SUMMARY OF FINDINGS

Asbestos: Asbestos-containing materials (ACM) were confirmed or assumed to be present as follows:

- Building B - Vinyl floor tiles;
- Building B – Transite (asbestos-cement) pipe (assumed);
- Buildings A & B - Roofing material (assumed);
- Building A & B - Exterior caulking (assumed).

Lead: Lead is present in paints and may be present in emergency light batteries.

Silica: Crystalline silica is present in concrete, mortar, brick, masonry, ceramics, asphalt, etc., where present in the building.

Mercury: Mercury vapour is present in fluorescent lamps throughout the building.

SUMMARY OF RECOMMENDATIONS

The following is a summary of significant recommendations; refer to the body of the report for detailed recommendations.

1. Perform a pre-construction survey and remove all ACM prior to alteration or maintenance work or if ACM may be disturbed by the work.
2. Remove and dispose of mercury-containing items when taken out of service.



3. Follow appropriate safe work procedures when handling or disturbing asbestos, lead, mercury and silica.

Please refer to Section 4.0 of this report for detailed recommendations regarding administrative and remedial actions.

This Executive Summary is subject to the same standard limitations as contained in the report and must be read in conjunction with the entire report.



Designated Substances Survey Report

Forensic Identification Unit – Building A and Radio & Electronic Services – Building B
2050 Jane Street, Toronto, ON
The City of Toronto

November 25, 2015

Pinchin File: 103037

FINAL

TABLE OF CONTENTS

1.0	INTRODUCTION AND SCOPE	1
1.1	Scope of Survey	1
2.0	BACKGROUND INFORMATION	2
2.1	Building Description	2
3.0	FINDINGS	2
3.1	Asbestos	2
3.2	Lead	9
3.3	Silica	10
3.4	Mercury	10
3.5	Polychlorinated Biphenyls	10
3.6	Mould	11
4.0	RECOMMENDATIONS	11
4.1	General	11
4.2	On-going Management and Maintenance	11
5.0	LIMITATIONS	12
6.0	REFERENCES	12

APPENDICES

APPENDIX I	Drawings
APPENDIX II-A	Asbestos Analytical Certificates
(No Information to Report)	
APPENDIX II-B	Lead Analytical Certificates
APPENDIX II-C	PCB Analytical Certificates
(No Information to Report)	
APPENDIX III	Methodology
APPENDIX IV	Photographs
(No Information to Report)	
APPENDIX V	Survey Form



Designated Substances Survey Report

Forensic Identification Unit – Building A and Radio & Electronic Services – Building B
2050 Jane Street, Toronto, ON
The City of Toronto

November 25, 2015

Pinchin File: 103037

FINAL

1.0 INTRODUCTION AND SCOPE

The City of Toronto (Client) retained Pinchin Ltd. (Pinchin) to conduct a Designated Substances Survey of Forensic Identification Unit – Building A and Radio & Electronic Services – Building B, located at 2050 Jane Street, Toronto, ON. The site consists of two buildings which are occupied by the Forensic Identification Unit (Building A) and Radio and Electronic Services (Building B).

The survey was performed by John Edwards, B.A., PCEM, Senior Project Technologist on May 13, 2015. The surveyor was accompanied by a representative of the City of Toronto during the survey. The buildings were occupied at the time of the survey.

The objective of the survey was to document the locations of specified Designated Substances, polychlorinated biphenyls (PCBs) and mould, evaluate their condition, and develop corrective action plans as required. This survey is only to be used for the purposes of long term management and routine maintenance. The results of this survey are not to be used for construction, renovation, demolition or project tendering purposes.

1.1 Scope of Survey

The survey was performed to review the location and type of specified hazardous building materials present in the building.

For the purpose of the survey and this report, hazardous building materials include the following Designated Substances:

- Asbestos
- Lead
- Silica
- Mercury

The survey also included:

- Polychlorinated Biphenyls (PCBs)
- Mould

The following Ontario Designated Substances are not typically found in building materials in a composition/state that is hazardous and were not included in this survey:

- Arsenic
- Acrylonitrile
- Benzene



Designated Substances Survey Report

Forensic Identification Unit – Building A and Radio & Electronic Services – Building B
2050 Jane Street, Toronto, ON
The City of Toronto

November 25, 2015

Pinchin File: 103037

FINAL

- Coke oven emissions
- Ethylene oxide
- Isocyanates
- Vinyl chloride monomer

2.0 BACKGROUND INFORMATION

2.1 Building Description

Item	Details
Building Use	Police Services and garage
Number of Floors/Levels	Building A: 1 storey, Building B: 2 stories
Total Area of Building (Square Feet)	78,000
Year of Construction	1980
Structure	Structural steel, concrete
Exterior Cladding	Brick, pre-cast concrete
HVAC	Rooftop units
Roof	Built-up roofing
Flooring	Vinyl tile, vinyl sheet flooring, concrete, carpet, ceramic tiles
Interior Walls	Drywall, concrete block
Ceilings	Drywall, acoustic ceiling tiles

3.0 FINDINGS

3.1 Asbestos

3.1.1 Suspect Building Materials Not Found

The following types of building materials may historically contain asbestos but were not observed in the building and are not discussed in the report findings:

- Texture finishes (acoustic/decorative)
- Plaster
- Firestopping

3.1.2 *Spray-Applied Fireproofing and Thermal Insulation*

Spray-applied fireproofing and overspray present on the structure of Buildings A and B was previously sampled (ECOH Management Inc. 2005) and found not to contain asbestos.



Sprayed fireproofing Building A



Sprayed fireproofing Building B

3.1.3 *Thermal Systems Insulation (TSI)*

3.1.3.1 *Pipe Insulation*

Non-asbestos insulation (e.g. fiberglass) is present on pipes throughout the assessed area.





Photo #3: Typical non-asbestos fiberglass pipe insulation.

3.1.3.2 *Duct Insulation*

Ducts are either uninsulated or insulated with non-asbestos fiberglass and jacketed with foil.



Typical non-asbestos fiberglass duct insulation

3.1.3.3 Mechanical Equipment Insulation

Mechanical equipment is either uninsulated or insulated with non-asbestos fibreglass

3.1.4 Acoustic Ceiling Tiles

Four distinct types of acoustic ceiling tile are present in the assessed area, as follows:

Size, Type, Pattern, Photo #	Sample Number or Date Code	Asbestos Type
ACT01, 24"x48", lay-in, random holes	Building B (ECOH Management Inc. 2005)	None detected
ACT02, 24"x48", lay-in, random fleck and holes	Building B (ECOH Management Inc. 2005)	None detected
ACT03, 24"x48", lay-in, random dimple and holes	Building A (Fisher Environmental Ltd. 2009)	None detected
ACT04, 24"x48", lay-in, random pinhole pattern	Building A (ECOH Management Inc. 2005)	None detected



ACT01



ACT02



ACT03



ACT04

3.1.5 Drywall Joint Compound

Drywall (gypsum board) and drywall joint compound is present as a wall and ceiling finish throughout Building A and B. Four samples previously collected from Building A (Fisher Environmental Ltd. 2009) and six samples collected from Building B (Pinchin 2012, 2014), were found to be non-asbestos.

3.1.6 Asbestos Cement Products (Transite)

Transite pipe is present as rain water leaders in Building B. Transite is assumed to contain asbestos based on visual observation. Transite is non-friable and in good condition.



Asbestos-containing Transite pipe in Building B.

3.1.7 Vinyl Sheet Flooring

Vinyl sheet flooring is present as follows:

Pattern, Colour and Photo Number	Paper Backing (Yes/No)	Sample Number	Asbestos Type
VSF01: Mixed shades of beige	No	Building A, 2014-A002A-C	None detected
VSF02: Mixed shades of blue	No	Building A, 2014-A003A-C	None detected
VSF03: Beige with black streaks	No	Building A, 2014-A004A-C	None detected
VSF04: Mixed shades of orange	No	Building A, 2014-A005A-C	None detected
VSF05: 24"x24" Marble Pattern	No	Building B, 2014-A011A-C	None detected



VSF01



VSF02



VSF03



VSF04



VST05

3.1.8 Vinyl Floor Tile and Mastic

Vinyl floor tiles are present as follows:

Size, Pattern, Colour and Photo Number	Sample Number	Asbestos Type (tile)	Asbestos Type (mastic)
VFT01: 12"x12", mixed shades of beige	Building A - 2014-A001A-C	None detected	None detected
VFT02: 12"x12", brown with white and beige smears	Building B - 2014-A006A-C	2% Chrysotile	None detected
VFT03: 12"x12", white with black streaks	Building B - 2014-A008A-C	3% Chrysotile	None detected
VFT04: 12"x12", mixed shades of beige	Building B - 2014-A012A-C	2% Chrysotile	None detected

Size, Pattern, Colour and Photo Number	Sample Number	Asbestos Type (tile)	Asbestos Type (mastic)
VFT05: 12"x12", black with white streaks	Building B - 2014-A010A-C	3% Chrysotile	None detected
VFT06: 24"x24", marble with black	Building B - 2014-A007A-C	None detected	None detected

The vinyl floor tiles and mastic are non-friable and are in good condition.



VFT02



VFT03



VFT04



VFT05

3.1.9 Assumed Asbestos Materials

A number of materials which might contain asbestos were not sampled during our survey due to limitations in scope and methodology. Where present, these materials must be assumed to be an asbestos material and are best sampled during project planning and preparation of contract documents for their removal. Materials assumed to contain asbestos include:

- roofing, felts and tar

- concrete floor levelling compound
- electrical components or wiring within control centers, breakers, motors or lights, insulation on wiring
- vermiculite in concrete block wall cavities
- adhesives and duct mastics
- caulking
- mechanical packing, ropes and gaskets
- fire resistant doors

3.2 Lead

3.2.1 Paints

One paint chip sample was collected from an interior painted finishes. Sample analysis determined the paint contains less lead than the City of Toronto action limit of 0.1%.

The following table summarized the sample analytical result and the sampling location. Appendix II-B presents the analytical results.

Sample Number	Colour, Substrate Description	Locations	Lead (%)
2015-L001	Red on concrete floor	Building A Mechanical Room (1-007)	<0.007



Red paint on concrete floor in Location 1-007 (Sample: 2015-L001).

3.2.2 Lead Products and Applications

Lead-containing batteries may be present in emergency lighting present throughout both buildings.



Emergency lighting with lead-containing battery

3.2.3 Assumed Lead Materials

Lead may be present in a number of materials which were not assessed and/or sampled. The following materials, where found, should be considered to contain lead.

- electrical components, including wiring connectors, fibre optic cable sheathing, grounding conductors, and solder

3.3 Silica

Crystalline silica is assumed component of the following building materials where present in the building:

- poured or pre-cast concrete
- masonry and mortar
- ceramic tiles, grout

3.4 Mercury

3.4.1 Lamps

Mercury vapour is present in fluorescent lamps where present in the assessed area.

3.4.2 Mercury-Containing Devices

Mercury-containing devices were not found during the survey.

3.5 Polychlorinated Biphenyls

3.5.1 Lighting Ballasts

Based on the age of the building (i.e. 1980) and confirmed by visual observations (evidence of T-8 fixtures) light fixtures are not suspect to contain PCB ballasts.

3.5.2 Transformers

All transformers in the building are dry type transformers and do not contain PCB-containing dielectric fluids.

3.6 Mould

Visible mould growth was not found in the assessed area.

4.0 RECOMMENDATIONS

4.1 General

Perform a detailed intrusive survey prior to building renovation or demolition operations. The survey should include; destructive testing (i.e. coring and/or removal of building finishes and components), and sampling of materials not previously tested (i.e. roofing materials, caulking, mastics).

4.2 On-going Management and Maintenance

The following recommendations are made regarding on-going management and maintenance work involving the hazardous materials identified.

4.2.1 Asbestos

Perform an assessment of asbestos materials on an annual basis. The next assessment of ACM should be performed prior to May 13, 2016 to remain in compliance.

Remove all asbestos-containing materials (ACM) prior to alteration or maintenance work or if ACM may be disturbed by the work. Follow appropriate asbestos precautions for the classification of work being performed.

Update the asbestos inventory report upon completion of any abatement and removal of asbestos-containing materials.

4.2.2 Lead

Lead-containing items should be recycled when taken out of service.

4.2.3 Silica

Disturbance of silica-containing products during maintenance activities may result in excessive exposures to airborne silica, especially if performed indoors and dry. Cutting, grinding, drilling or demolition of materials containing silica should be completed only with proper respiratory protection and other worker safety precautions that comply with provincial standards or guidelines.



Designated Substances Survey Report

Forensic Identification Unit – Building A and Radio & Electronic Services – Building B
2050 Jane Street, Toronto, ON
The City of Toronto

November 25, 2015

Pinchin File: 103037

FINAL

4.2.4 Mercury

Recycle and reclaim mercury from fluorescent light tubes and thermostats when taken out of service. Do not break lamps or separate liquid mercury from components. Light tubes are accepted free of charge at many local recycling depots. Liquid mercury is classified as a hazardous waste and must be disposed of in accordance with local regulations.

5.0 LIMITATIONS

The work performed by Pinchin was conducted in accordance with the City of Toronto Contract Number 47018468, effective July 31, 2014.

6.0 REFERENCES

The following legislation and documents were referenced in completing the survey and this report:

1. Asbestos on Construction Projects and in Buildings and Repair Operations, Ontario Regulation 278/05.
2. Designated Substances, Ontario Regulation 490/09.
3. Lead on Construction Projects, Ministry of Labour Guidance Document.
4. Ministry of the Environment Regulation, R.R.O. 1990 Reg. 347 as amended.
5. Surface Coating Materials Regulations, SOR/2005-109, Hazardous Products Act.
6. Silica on Construction Projects, Ministry of Labour Guidance Document.
7. Alert – Mould in Workplace Buildings, Ontario Ministry of Labour.
8. Standard Operating Procedures for Designated Substance Surveys, dated April, 2014, City of Toronto, Facilities Management.

\\pinchin.com\miss\Job\103000s\103037 CITYOFTORONTO,VariousLocati,DSUB,ASSMT\Toronto Police Services\2050 Jane Street\Report\FINAL\2050 Jane St_DSS_2015.docx

Template: Master Report for Hazardous Materials Assessment Report (Tablet Management), Haz, December 10, 2014

APPENDIX I
Drawings



LEGEND:

- 1-01 LOCATION NUMBER
- ASBESTOS BULK SAMPLE
- LEAD BULK SAMPLE
- CONFIRMED AND/OR ASSUMED
ASBESTOS-CONTAINING MATERIAL

NOT ALL KNOWN OR ASSUMED DESIGNATED
SUBSTANCES ARE IDENTIFIED ON THE
DRAWING. REFER TO THE DESIGNATED
SUBSTANCE REPORT FOR A COMPLETE LIST
OF KNOWN AND ASSUMED DESIGNATED
SUBSTANCES.



CLIENT:

CITY OF TORONTO

LOCATION:
FORENSIC IDENTIFICATION UNIT - BUILDING A
2050 JANE STREET
TORONTO, ONTARIO

TITLE:
DESIGNATED SUBSTANCES
SURVEY
GROUND FLOOR

DATE: 2015/05/13	PROJECT # : 103037
DRAWN BY: BW	1 OF 3
CHECKED BY: JE	
SCALE: NTS	





LEGEND:

- 1-01

LOCATION NUMBER
- ASBESTOS BULK SAMPLE
- LEAD BULK SAMPLE
- CONFIRMED AND/OR ASSUMED
ASBESTOS-CONTAINING MATERIAL

NOT ALL KNOWN OR ASSUMED DESIGNATED SUBSTANCES ARE IDENTIFIED ON THE DRAWING. REFER TO THE DESIGNATED SUBSTANCE REPORT FOR A COMPLETE LIST OF KNOWN AND ASSUMED DESIGNATED SUBSTANCES.

CLIENT:

CITY OF TORONTO

LOCATION:

RADIO AND ELECTRONIC SERVICES - BUILDING B
2050 JANE STREET
TORONTO, ONTARIO

TITLE:

DESIGNATED SUBSTANCES
SURVEY
GROUND FLOOR

DATE:

2015/05/13

PROJECT # :

103037

DRAWN BY:

BW

CHECKED BY:

JE

SCALE:

NTS

DRAWING:


2 OF 3



BUILDING B



LEGEND:	
1-01	LOCATION NUMBER
	ASBESTOS BULK SAMPLE
	LEAD BULK SAMPLE
	CONFIRMED AND/OR ASSUMED ASBESTOS-CONTAINING MATERIAL
NOT ALL KNOWN OR ASSUMED DESIGNATED SUBSTANCES ARE IDENTIFIED ON THE DRAWING. REFER TO THE DESIGNATED SUBSTANCE REPORT FOR A COMPLETE LIST OF KNOWN AND ASSUMED DESIGNATED SUBSTANCES.	
CLIENT:	
CITY OF TORONTO	
LOCATION:	
RADIO AND ELECTRONIC SERVICES - BUILDING B 2050 JANE STREET TORONTO, ONTARIO	
TITLE:	
DESIGNATED SUBSTANCES SURVEY SECOND FLOOR	
DATE:	PROJECT # :
2015/05/13	103037
DRAWN BY:	DRAWING:
BW	
CHECKED BY:	
JE	3 OF 3
SCALE:	
NTS	



BUILDING B

APPENDIX II-A
Asbestos Analytical Certificates
(No Information to Report)

APPENDIX II-B
Lead Analytical Certificates



Analysis for Lead Concentration in Paint Chips

by Flame Atomic Absorption Spectroscopy
EPA SW-846 3050B/6010C/7420



Customer: Pinchin Ltd.
2470 Milltower Court
Mississauga ON L5N 7W5

Attn: John Edwards
Juliette McIntyre

Lab Order ID: 1509575
Analysis ID: 1509575_PBP
Date Received: 5/18/2015
Date Reported: 5/26/2015

Project: 2050 Jane St. Building A

Sample ID	Description	Mass (g)	Concentration (ppm)	Concentration (% by weight)
Lab Sample ID	Lab Notes			
2015-L001	Red paint on concrete - 1-007	0.0559	< 72	< 0.007%
1509575PBP_1				

Unless otherwise noted blank sample correction was not performed on analytical results. Scientific Analytical Institute participates in the AIHA IHPAT program. IHPAT Laboratory ID: 173190. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. Analytical uncertainty available upon request. The quality control samples run with the samples in this report have passed all EPA required specifications unless otherwise noted. RL: (Report Limit for an undiluted 50ml sample is 4µg Total Pb).

Daniel Olson (1)

Analyst

Laboratory Director

1509575

Version 1-15-2012

Client:	Pinchin Ltd.	*Instructions: Use Column "B" for your contact info To See an Example Click the bottom Example Tab. Enter samples between "<<" and ">>" Begin Samples with a "<<" above the first sample and end with a ">>" below the last sample. Only Enter your data on the first sheet "Sheet1"	Invoice to:
Contact:	John Edwards		Juliette McIntyre
Address:	2470 Milltower court		jmcintyre@pinchin.com
Phone:	905-363-0678		
Fax:	905-363-0681		
Email:	jedwards@pinchin.com jmcintyre@pinchin.com		Scientific Analytical Institute 
Project:	2050 Jane St. Building A		
Client Notes:	[Enter Client Notes Here]		
P.O. #:	103037		
Date Submitted:	5/15/2015 0:00	Note: Data 1 and Data 2 are optional fields that do not show up on the official report, however they will be included in the electronic data returned to you to facilitate your reintegration of the report data.	4604 Dundas Dr. Greensboro, NC 27407 Phone: 336.292.3888 Fax: 336.292.3313 Email: lab@sailab.com
Analysis:	Lead		
TurnAroundTime:	Regular		

Sample Number	Data 1 (Lab use only)	Sample Description	Data 2 (Lab use only)
<<			
2015-L001		Red paint on concrete - 1-007	

B. Hulley 5/18 10A

Accepted ☒

Rejected ☐

APPENDIX II-C
PCB Analytical Certificates
(No Information to Report)

APPENDIX III
Methodology



1.0 GENERAL

The following survey methodology is based on the requirements of the *Standard Operation Procedure for Designated Substance Surveys*, dated April, 2014, provided by the City of Toronto (the "SOP").

Pinchin conducted a room-by-room survey (rooms, corridors, service areas, exterior, etc.) to identify the hazardous building materials as defined in Section 1.1. Information regarding the approximate quantity, location, and condition of hazardous building materials encountered and visually estimated quantities were recorded on the *Survey Form*, provided by the City of Toronto, found in Appendix V. The locations of any samples collected were recorded on small-scale plans, found in Appendix I.

Drawings (i.e., floor plans), previous reports, and Survey Forms, were referenced where provided.

1.1 Limitations on Scope

The survey excludes the following:

- Owner or occupant articles (e.g. stored items, furniture, appliances, etc.);
- Underground materials or equipment (e.g. vessels, drums, underground storage tanks, pipes, etc.);
- Building envelope, structural components, inaccessible or concealed materials or other items where sampling may cause consequential damage to the property.
- Energized systems (e.g. internal boiler components, elevators, mechanical or electrical components);
- Controlled products (e.g. stored chemicals, operational or process-related substances); and
- Materials not typically associated with construction (e.g. settled dust, spills, residual contamination from prior spills, etc.).

The survey was limited to non-intrusive testing. Concealed spaces such as those above solid ceilings and within shafts and pipe chases were accessed via existing access panels only. Pinchin did not conduct demolition of walls, solid ceilings, structural items, interior finishes or exterior building finishes, to determine the presence of concealed materials.

1.2 Asbestos

Pinchin conducted an inspection for the presence of friable and non-friable asbestos-containing materials (ACM). A friable material is a material that when dry can be crumbled, pulverized or powdered by hand pressure.



Pinchin collected samples at a rate that is in compliance with Table 1 of O.Reg. 278/05. A separate set of samples was collected of each of homogenous material sampled. A homogenous material is defined by the US EPA¹ as material that is uniform in texture and appearance, was installed at one time, and is unlikely to consist of more than one type or formulation of material. The homogeneous materials are determined by visual examination, available information on the phases of the construction and prior renovations.

The following materials were sampled:

- All friable materials historically known to contain asbestos, regardless of year of installation, not identified in previous reports;
- Friable materials previously sampled in insufficient quantity to conclude the materials are non-asbestos, in accordance with the requirements of O.Reg. 278/05;
- Friable materials previously reported to contain less than 1% asbestos, if sampled prior to the Ministry of Labour defining an asbestos-containing material as a material containing contains 0.5 percent or more asbestos by weight;
- Non-friable acoustic ceiling tiles;
- Non-friable vinyl floor tiles and mastic.

The following materials were **not** sampled:

- Materials previously identified in previous reports provided as asbestos-containing;
- Materials previously confirmed to be non-asbestos in accordance with O.Reg. 278/05;
- Unless damaged the following materials were not sampled: plaster, drywall joint compound, mastic, window caulking, roofing materials, vinyl sheet flooring. Materials not sampled are assumed to contain asbestos.
- Materials where sampling poses an inherent, imminent danger to the Assessor such as high voltage wiring, materials present at heights greater than 12 feet, or those in confined spaces. These materials are assumed to be asbestos-containing.

In some cases, manufactured products such as asbestos cement pipe are visually identified without sample confirmation.

¹ Environmental Protection Agency



Pinchin submits the bulk samples to a NVLAP² accredited laboratory for analysis. The analysis is performed in accordance with Test Method EPA/600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials, July 1993.

The asbestos analysis is completed using a stop positive approach. Only one result of greater than the regulated criteria (0.5%) is required to determine that a material is asbestos-containing, but all samples must be analyzed to conclusively determine that a material is non-asbestos. The laboratory stops analyzing samples from a homogeneous material once a result greater than the regulated criteria is detected in any of the samples of that material. All samples of a homogeneous material are analyzed if no asbestos is detected. In some cases, all samples are analyzed in the sample set regardless of result. Where building materials are described in the report as non-asbestos, or described as containing no asbestos, this is subject to the limitations of the analytical method used, and should be understood to mean no asbestos was detected.

Asbestos materials are evaluated in order to make recommendations regarding remedial work. The priority for remedial action is based on several factors:

- friability (friable or non-friable).
- condition (good, fair, poor, debris, based on definitions in the SOP).
- accessibility (ranking from accessible to all building users to inaccessible).
- visibility (whether the material is obscured by other building components).
- efficiency of the work (for example, if damaged ACM is being removed in an area, it may be most practical to remove all ACM in the area even if it is in good condition).

This includes friability, condition and efficiency and practicality of the work.

1.3 Lead

Pinchin collected samples of damaged paint not identified in a previous report. Drawings included show sample locations.

Analysis for lead in paints or surface coatings is performed in accordance with EPA Method No. 3050B/Method No. 7420; flame atomic absorption at an accredited laboratory.

For this report, all paints containing lead at a concentration 0.1% or greater are discussed. Paint was evaluated for condition.

² National Voluntary Laboratory Accreditation Program

Lead building products (e.g. batteries, lead sheeting, flashing) are identified by visual observation only.

1.4 Silica

Pinchin identifies building materials suspected of containing crystalline silica (e.g. concrete, cement, tile, brick, masonry, mortar) by knowledge of current and historic applications and visual inspection only.

Pinchin does not perform sampling of these materials for laboratory analysis of crystalline silica content.

1.5 Mercury

Building materials/products/equipment (e.g. thermostats, barometers, pressure gauges, light tubes), suspected to contain mercury were identified by visual inspection only. Dismantling of equipment suspected of containing mercury was not performed. Sampling of these materials for laboratory analysis of mercury content was not performed.

Mercury spills or damaged mercury-containing equipment was recorded where observed.

1.6 Polychlorinated Biphenyls

Pinchin determines the potential for light ballast and wet transformers to contain PCBs based on the age of the building, a review of maintenance records and examination of labels or nameplates on equipment, where present and accessible. The information is compared to known ban dates of PCBs and Environment Canada publications.

Dry type transformers are assumed to be free of dielectric fluids and hence non-PCB.

Pinchin records spills or leakage of suspect PCB-containing fluids where observed or identified in historical documents.

Fluids (mineral oil, hydraulic or Askaral) in transformers or other equipment are not sampled for PCB content.

Non-liquid forms of PCBs (i.e. sealants or caulking) are not sampled for PCB content.

1.7 Visible Mould

Pinchin identifies the presence of mould if visibly present in a significant quantity on exposed building surfaces. If any mould growth is concealed within wall cavities it is not addressed in this survey.

APPENDIX IV

Photographs

(No Information to Report)



Photo #15: VSF03




Photo #16: VSF04



Photo #17: VSF05



Photo #18: VFT01



Photo #19: VFT04




Photo #20: VFT05

APPENDIX V
Survey Form

APPENDIX V - SURVEY FORM

Building Address		2050 Jane Street A and B,			Date(s) of Current Reassessment:		May 13, 2015		
Building Name		Forensic Identification Unit and Radio and Electronic Services			Organization completing Asbestos Reassessment:		Pinchin Ltd. - John Edwards		
Summary of Findings: Added asbestos-containing Transite pipe to Locations 1-018 & 1-019 in Building B Added lead paint sample (2015-L001) to Location 1-007 in Building A									
Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
<u>Forensic Identification Unit (Building A)</u>									
0-00	Exterior	Roof	Roofing Material	Asbestos	Not Sampled	ACM Assumed	200 m2	Good	
0-00	Exterior	Windows	Window Caulking	Asbestos	Not Sampled	ACM Assumed	20 m2	Good	
1-001	Second Floor Mechanical Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-001	Second Floor Mechanical Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-001	Second Floor Mechanical Room	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-002	Mezzanine above Car Bay 1	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-002	Mezzanine above Car Bay 1	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-002	Mezzanine above Car Bay 1	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-003	Mezzanine above Car Bay 2	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-003	Mezzanine above Car Bay 2	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-003	Mezzanine above Car Bay 2	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-004	Elevator	Floors	Carpet	N/A	N/A	N/A	N/A	N/A	
1-004	Elevator	Walls	Steel	N/A	N/A	N/A	N/A	N/A	
1-004	Elevator	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-005	Stairwell	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-005	Stairwell	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-005	Stairwell	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-006	Corridor	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-006	Corridor	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-006	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-006	Corridor	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-006	Corridor	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-006	Corridor	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B08-04 to 06	None Detected	N/A	N/A	
1-007	Sprinkler Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-007	Sprinkler Room	Floor	Paint	Lead	2015-L001	<0.007	N/A	N/A	Red floor paint
1-007	Sprinkler Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-007	Sprinkler Room	Ceiling	Concrete	N/A	N/A	N/A	N/A	N/A	
1-007	Sprinkler Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-007	Sprinkler Room	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B08-04 to 06	None Detected	N/A	N/A	
1-008	Class Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-008	Class Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-008	Class Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 2005 Sample 11087-B08-01	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-008	Class Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-008	Class Room	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-009	Mechanical Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-009	Mechanical Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-009	Mechanical Room	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-009	Mechanical Room	Mechanical	Other	PCB	N/A	N/A	N/A	N/A	Transformer (dry type)
1-010	Mechanical Closet	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-010	Mechanical Closet	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-010	Mechanical Closet	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-010	Mechanical Closet	Mechanical	Other	PCB	N/A	N/A	N/A	N/A	Transformer (dry type)
1-011	Quiet Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-011	Quiet Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-011	Quiet Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-012	Caretaker Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-012	Caretaker Office	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-012	Caretaker Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-013	Corridor	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-013	Corridor	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-013	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-014	Storage Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-014	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-014	Storage Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-015	Negative Pressure Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-015	Negative Pressure Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-015	Negative Pressure Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-016	Waste Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-016	Waste Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-016	Waste Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-017	Storage Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-017	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-017	Storage Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-017	Storage Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-018	Entrance	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-018	Entrance	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-018	Entrance	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-019	Lab Entrance	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-019	Lab Entrance	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-019	Lab Entrance	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-020	Car Bay 1	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-020	Car Bay 1	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-020	Car Bay 1	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-020	Car Bay 1	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-021	Car Bay 2	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-021	Car Bay 2	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-021	Car Bay 2	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-021	Car Bay 2	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-022	Body Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-022	Body Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-022	Body Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-023	Storage Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-023	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-023	Storage Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-024	Triage	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-024	Triage	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-024	Triage	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-024	Triage	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-024	Triage	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-025	Finger Print Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A003A-C	None Detected	N/A	N/A	VSF-02, mixed shades of blue.
1-025	Finger Print Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-025	Finger Print Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-026	Lab	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A003A-C	None Detected	N/A	N/A	VSF-02, mixed shades of blue.
1-026	Lab	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-026	Lab	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-027	Corridor	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A003A-C	None Detected	N/A	N/A	VSF-02, mixed shades of blue.
1-027	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-027	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-027	Corridor	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-027	Corridor	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-028	Evidence Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A003A-C	None Detected	N/A	N/A	VSF-02, mixed shades of blue.
1-028	Evidence Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-028	Evidence Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-029	Closet	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-029	Closet	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-029	Closet	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-030	Evidence Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A003A-C	None Detected	N/A	N/A	VSF-02, mixed shades of blue.
1-030	Evidence Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-030	Evidence Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-031	Document Section	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A003A-C	None Detected	N/A	N/A	VSF-02, mixed shades of blue.
1-031	Document Section	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-031	Document Section	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-032	Shift Personal	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A003A-C	None Detected	N/A	N/A	VSF-02, mixed shades of blue.
1-032	Shift Personal	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-032	Shift Personal	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-033	Closet	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-033	Closet	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-033	Closet	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-034	Corridor	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-034	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-034	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-034	Corridor	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-034	Corridor	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-035	Fire Suppression Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-035	Fire Suppression Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-035	Fire Suppression Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-036	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-036	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-036	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-037	Photo Lab	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-037	Photo Lab	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-037	Photo Lab	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-038	Computer Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-038	Computer Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-038	Computer Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-039	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-039	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-039	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-039	Office	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-039	Office	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-040	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-040	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-040	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-040	Office	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-040	Office	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-041	AFIS Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-041	AFIS Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-041	AFIS Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-041	AFIS Office	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-042	Corridor	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-042	Corridor	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-042	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-043	Finger Print Storage	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-043	Finger Print Storage	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-043	Finger Print Storage	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-044	Corridor	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-044	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-044	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-045	Lamination Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014A004A-C	None Detected	N/A	N/A	VSF-03, beige with black streaks.
1-045	Lamination Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-045	Lamination Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-045	Lamination Room	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-046	Printing Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014A004A-C	None Detected	N/A	N/A	VSF-03, beige with black streaks.
1-046	Printing Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-046	Printing Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-047	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-047	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-047	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-048	Storage Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-048	Storage Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-048	Storage Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-049	Film Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-049	Film Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-049	Film Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-050	Photo Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A003A-C	None Detected	N/A	N/A	VSF-02, mixed shades of blue.
1-050	Photo Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-050	Photo Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-051	Photo Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A003A-C	None Detected	N/A	N/A	VSF-02, mixed shades of blue.
1-051	Photo Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-051	Photo Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-052	Storage Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A003A-C	None Detected	N/A	N/A	VSF-02, mixed shades of blue.
1-052	Storage Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-052	Storage Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-053	Corridor	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-053	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-053	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-054	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-054	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-054	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-055	Office	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-055	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-055	Office	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-056	Quality Control	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-056	Quality Control	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-056	Quality Control	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-056	Quality Control	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-056	Quality Control	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-056	Quality Control	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-057	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-057	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-057	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-058	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-058	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-058	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-059	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-059	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-059	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-060	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-060	Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-060	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-061	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-061	Office	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-061	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-061	Office	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-062	Storage Room	Floor	Carpet	Asbestos	N/A	N/A	N/A	N/A	
1-062	Storage Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-062	Storage Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-063	Entrance	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-063	Entrance	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-063	Entrance	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-064	Storage Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-064	Storage Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-064	Storage Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2009 Sampled 1 to 3	None Detected	N/A	N/A	ACT-03, 24"x48" random dimple and hole
1-065	Office Area	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-065	Office Area	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-065	Office Area	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-065	Office Area	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-066	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-066	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-066	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-67	Phone Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-67	Phone Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-67	Phone Room	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-068	Gun Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-068	Gun Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-068	Gun Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-069	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-069	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-069	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-070	Storage Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-070	Storage Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-070	Storage Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-071	Storage Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-071	Storage Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-071	Storage Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-072	Gym	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-072	Gym	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-072	Gym	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-073	Storage Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-073	Storage Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-073	Storage Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-074	Lunch Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A005A-C	None Detected	N/A	N/A	VSF-04, mixed shades of orange
1-074	Lunch Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-074	Lunch Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-074	Lunch Room	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-075	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-075	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-075	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-075	Office	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-076	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-076	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-076	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-076	Office	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-077	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-077	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-077	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-077	Office	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-078	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-078	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-078	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-079	Copy Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-079	Copy Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-079	Copy Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-080	Supply Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-080	Supply Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-080	Supply Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-081	Women's Locker Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-081	Women's Locker Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-081	Women's Locker Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-082	Women's Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-082	Women's Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-082	Women's Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-083	Men's Locker Room	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A002A-C	None Detected	N/A	N/A	VSF-01, mixed shades of beige
1-083	Men's Locker Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-083	Men's Locker Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-084	Men's Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-084	Men's Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-084	Men's Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-085	Property Storage	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-085	Property Storage	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-085	Property Storage	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-086	Electrical Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-086	Electrical Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-086	Electrical Room	Ceilings	Concrete	N/A	N/A	N/A	N/A	N/A	White mastic on ducts
1-087	SGT's Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-087	SGT's Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-087	SGT's Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B08-01 to 03	None Detected	N/A	N/A	ACT-04, 24"x48" random pinhole pattern
1-088	Evidence Handling Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-088	Evidence Handling Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-088	Evidence Handling Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	NAC
1-089	Evidence Handling Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A001A-C	None Detected	N/A	N/A	VFT-01, 12"x12" mixed shades of beige.
1-089	Evidence Handling Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2009 Sample 4 to 7	None Detected	N/A	N/A	
1-089	Evidence Handling Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - 0001A-C	None Detected	N/A	N/A	NAC
<u>Radio and Electronic Services (Building B)</u>									
0-00	Exterior	Roof	Roofing Material	Asbestos	Not Sampled	None Detected	20 m2	Good	
0-00	Exterior	Windows	Window Caulking	Asbestos	Not Sampled	None Detected	2 m2	Good	
1-001	Car Bay	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-001	Car Bay	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-001	Car Bay	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-001	Car Bay	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-002	Stairwell	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A006A-C	2% Chrysotile	8 m2	Good	VFT-02 12"x12" brown with white and beige smears, tile only acm
1-002	Stairwell	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
1-002	Stairwell	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
1-002	Stairwell	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-003	Telecom Stock Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A007A-C	None Detected	N/A	N/A	VFT-06 24"x24" mable with black veins

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-003	Telecom Stock Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-003	Telecom Stock Room	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-003	Telecom Stock Room	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-004	Elevator	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-004	Elevator	Walls	Steel	N/A	N/A	N/A	N/A	N/A	
1-004	Elevator	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-005	Corridor	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A006A-C	2% Chrysotile	20 m2	Good	VFT-02 12"x12" brown with white and beige smears, tile only acm
1-005	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
1-005	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
1-005	Corridor	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-006	Stock Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A007A-C	None Detected	N/A	N/A	VFT-06 24"x24" maple with black veins
1-006	Stock Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-006	Stock Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-006	Stock Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
1-006	Stock Room	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-007	Service Floor	Floor	Concrete	Asbestos	N/A	N/A	N/A	N/A	
1-007	Service Floor	Walls	Concrete Block	Asbestos	N/A	N/A	N/A	N/A	
1-007	Service Floor	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	
1-007	Service Floor	Ceiling	Steel	Asbestos	N/A	N/A	N/A	N/A	
1-007	Service Floor	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-007	Service Floor	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-008	Office	Floor	Carpet	Asbestos	N/A	N/A	N/A	N/A	
1-008	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	Good	
1-008	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-008	Office	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-009	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-009	Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
1-009	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	NAC
1-010	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A006A-C	2% Chrysotile	10 m2	Good	VFT-02 12"x12" brown with white and beige smears, tile only acm
1-010	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
1-010	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
1-010	Office	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-011	Repair Services	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A011A-C	None Detected	N/A	N/A	VSF-05 24"x24" marble pattern
1-011	Repair Services	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
1-011	Repair Services	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
1-011	Repair Services	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-012	Chiller Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014A008A-C	3% Chrysotile	8 m2	Good	VFT-03, 12"x12" white with black streaks, tile only acm
1-012	Chiller Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-012	Chiller Room	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-013	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A007A-C	None Detected	N/A	N/A	VFT-06 24"x24" mable with black veins
1-013	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
1-013	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
1-013	Office	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-014	Telephone Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-014	Telephone Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-014	Telephone Room	Ceiling	Concrete	N/A	N/A	N/A	N/A	N/A	
1-015	Corridor	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-015	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-015	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
1-015	Corridor	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-015	Corridor	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-016	Stairwell	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	15 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
1-016	Stairwell	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	Good	
1-016	Stairwell	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
1-017	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A006A-C	2% Chrysotile	7.5 m2	Good	VFT-02 12"x12" brown with white and beige smears, tile only acm
1-017	Office	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-017	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
1-017	Office	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-018	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	10 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
1-018	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
1-018	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole
1-018	Office	Piping	Transite	Asbestos	Visually identified	ACM Assumed	10 LF	Good	
1-019	Front Desk	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	30 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
1-019	Front Desk	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
1-019	Front Desk	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole
1-019	Front Desk	Piping	Transite	Asbestos	Visually identified	ACM Assumed	30 LF	Good	
1-020	Corridor	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-020	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
1-020	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole
1-020	Corridor	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-020	Corridor	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-021	Stairwell	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	15 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
1-021	Stairwell	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-021	Stairwell	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48"" random fleck and hole
1-022	Women's Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-022	Women's Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
1-022	Women's Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	NAC
1-023	Janitor Closet	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-023	Janitor Closet	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-023	Janitor Closet	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	NAC
1-023	Janitor Closet	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-024	Men's Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-024	Men's Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
1-024	Men's Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	NAC
1-024	Men's Washroom	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-025	Lunch Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	20 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
1-025	Lunch Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
1-025	Lunch Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48"" random fleck and hole
1-025	Lunch Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-026	Shop	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-026	Shop	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-026	Shop	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-026	Shop	Piping	Transite	Asbestos	Visually identified	ACM Assumed	20 LF	Good	
1-026	Shop	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-027	File Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-027	File Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-027	File Room	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-028	Machine Shop	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-028	Machine Shop	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-028	Machine Shop	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-029	Compressor Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-029	Compressor Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-029	Compressor Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	NAC
1-030	Truck Wash Bay	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-030	Truck Wash Bay	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-030	Truck Wash Bay	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-030	Truck Wash Bay	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-031	Clothing Storage	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	40 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
1-031	Clothing Storage	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-031	Clothing Storage	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-031	Clothing Storage	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-032	Tire Storage	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-032	Tire Storage	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-032	Tire Storage	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-033	Clothing Storage	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	50 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
1-033	Clothing Storage	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-033	Clothing Storage	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-033	Clothing Storage	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-034	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	Ceramic
1-034	Washroom	Walls	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-034	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	NAC
1-035	Corridor	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-035	Corridor	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-035	Corridor	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-035	Corridor	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-036	Storage	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A007A-C	None Detected	N/A	N/A	VFT-06 24"x24" mable with black veins
1-036	Storage	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-036	Storage	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-036	Storage	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-037	Quick Service Garage	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-037	Quick Service Garage	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-037	Quick Service Garage	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-038	Parts Counter	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	10 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
1-038	Parts Counter	Wall	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-038	Parts Counter	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-038	Parts Counter	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-039	Parts Storage	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	120 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
1-039	Parts Counter	Wall	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-039	Parts Storage	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-039	Parts Storage	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-040	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	10 m2	N/A	VFT-04, 12"x12" mixed shades of beige, tile only acm
1-040	Office	Walls	Concrete Block	Asbestos	N/A	N/A	N/A	N/A	
1-040	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
1-041	Stairwell	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
1-041	Stairwell	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-041	Stairwell	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-042	Fitting Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-042	Fitting Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-042	Fitting Room	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-042	Fitting Room	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
1-043	Tailor Shop	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-043	Tailor Shop	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-043	Tailor Shop	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
1-043	Tailor Shop	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
2-001	Training Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A007A-C	None Detected	N/A	N/A	VFT-06 24"x24" mable with black veins
2-001	Training Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-001	Training Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-002	Corridor	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	100 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-002	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	Good	
2-002	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-003	Lunch Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A006A-C	2% Chrysotile	30 m2	Good	VFT-02 12"x12" brown with white and beige smears, tile only acm
2-003	Lunch Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-003	Lunch Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-003	Lunch Room	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
2-004	Men's Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
2-004	Men's Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-004	Men's Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	NAC
2-005	Janitor Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
2-005	Janitor Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
2-005	Janitor Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	NAC
2-005	Janitor Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
2-006	Women's Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
2-006	Women's Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-006	Women's Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	NAC
2-007	Copy Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A010A-C	3% Chrysotile	20 m2	Good	VFT-05, 12"x12" Black with white streaks, tile only acm
2-007	Copy Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-007	Copy Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-008	Office	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A011A-C	None Detected	N/A	N/A	VSF-05 24"x24" marble pattern
2-008	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-008	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole
2-009	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	20 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-009	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-009	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole
2-010	Office	Floor	Vinyl Sheet Flooring (VSF)	Asbestos	2014 A011A-C	None Detected	N/A	N/A	VSF-05 24"x24" marble pattern
2-010	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-010	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole
2-011	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A007A-C	None Detected	N/A	N/A	VFT-06 24"x24" mable with black veins
2-011	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-011	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole
2-012	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-012	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-012	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
2-013	Repair Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	25 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-013	Repair Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-013	Repair Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole
2-013	Repair Office	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
2-014	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	10 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-014	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-014	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B10-01 to 03	None Detected	N/A	N/A	ACT-02, 24"x48" random fleck and hole
2-015	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	10 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-015	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-015	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-016	Stairwell	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	10 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-016	Stairwell	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-016	Stairwell	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-017	Corridor	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	100 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-017	Corridor	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
2-017	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-017	Corridor	Ducts	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
2-018	Unit Commander	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
2-018	Unit Commander	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-018	Unit Commander	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-019	Clerks Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	15 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-019	Clerks Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-019	Clerks Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-020	Lunch Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	10 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
2-020	Lunch Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
2-020	Lunch Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-021	Office	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
2-021	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-021	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-022	Admin Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	10 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-022	Admin Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
2-022	Admin Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-023	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-023	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-023	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-024	Meeting Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	30 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-024	Meeting Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2012 A001A-C	None Detected	N/A	N/A	
2-024	Meeting Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-025	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	20 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-025	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
2-025	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-026	Gym	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2014 A012A-C	2% Chrysotile	40 m2	Good	VFT-04, 12"x12" mixed shades of beige, tile only acm
2-026	Gym	Walls	Drywall Joint Compound (DJC)	Asbestos	Sampled 2012 - A0001A-C	None Detected	N/A	N/A	
2-026	Gym	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes
2-026	Gym	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
2-027	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-027	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
2-027	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2005 Sample 11087-B09-09 to 11	None Detected	N/A	N/A	ACT-01, 24"x48" random holes

APPENDIX V - SURVEY FORM

Location Number	Location Name	Building System	Potential ACM Observed	Potential Hazardous Materials	Sample ID	Analytical Result	Quantity	Condition	Notes/Required Action
2-028	Quite Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-028	Quite Room	Walls	Drywall Joint Compound (DJC)	Asbestos	2014 A009A-C	None Detected	N/A	N/A	
2-028	Quite Room	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
2-029	Storage Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
2-029	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
2-029	Storage Room	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
2-029	Storage Room	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
2-030	Storage Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
2-030	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
2-030	Storage Room	Ceiling	Steel	N/A	N/A	N/A	N/A	N/A	
2-030	Storage Room	Structure	Sprayed Fireproofing	Asbestos	2005 Sample 11087-B09-01 to 05	None Detected	N/A	N/A	
Surveyor's Field Notes									
NAC = No Access Above Ceiling									