

FINAL

Designated Substances Survey Report

32 Division
30 Ellerslie Ave., Toronto, ON

Prepared for:

The City of Toronto

Facilities Management
55 John Street, 2nd Floor
Toronto ON

Attention: Sara Reid
Environmental Project Manager

December 4, 2015

Pinchin File: 103037



Designated Substances Survey Report

32 Division
30 Ellerslie Ave., Toronto, ON
The City of Toronto

December 4, 2015

Pinchin File: 103037

FINAL

Issued to: The City of Toronto
Contact: Sara Reid
Environmental Project Manager
Issued on: December 4, 2015
Pinchin file: 103037
Issuing Office: 50 Wellington Street East, Suite
200, Toronto, ON M5E 1C8
Primary Contact: Juliette McIntyre

Reviewer: Juliette McIntyre
Senior Project Manager
jmcintyre@pinchin.com

Reviewer: Mark Stroombergen, C.E.T.
Director, GTA - Hazardous Materials
mstroombergen@pinchin.com



EXECUTIVE SUMMARY

The City of Toronto (Client) retained Pinchin Ltd. (Pinchin) to conduct a Designated Substance survey of the Police Services 32 Division located at 30 Ellerslie Ave., Toronto, ON. The survey was performed on June 4, 2015.

The objective of the survey was to document the locations of specified Designated Substances, polychlorinated biphenyls (PCBs) and mould, evaluate their condition, and develop corrective action plans as required for the purposes of long term management. The results of this survey are not intended for construction, renovation, demolition or project tendering purposes.

The survey area consisted of the entire building. The building was occupied at the time of the survey.

SUMMARY OF FINDINGS

Asbestos: Asbestos-containing materials (ACM) were confirmed or assumed to be present as follows:

- Parging cement insulation on pipe fittings of the hot water heating system;
- Drywall throughout building (assumed);
- Plaster throughout building (assumed);
- Roofing material (assumed);
- Window caulking (assumed).

Lead: Lead was confirmed present in paint sampled at <0.1%. Paints not sampled are assumed to contain lead. Lead may be present in emergency light batteries.

Silica: Crystalline silica is present in concrete, mortar, brick, masonry, ceramics, asphalt, etc., where present in the building.

Mercury: Mercury vapour is present in fluorescent lamps throughout the building. Liquid mercury is present in thermostat ampules.

Polychlorinated Biphenyls (PCBs): PCBs may be present in light ballasts.

Mould: No visible mould-impacted materials were identified.

SUMMARY OF RECOMMENDATIONS

The following is a summary of significant recommendations; refer to the body of the report for detailed recommendations.



1. Perform a pre-construction survey and remove all ACM prior to alteration or maintenance work or if ACM may be disturbed by the work.
2. Remove and dispose of PCB ballasts and mercury-containing items when taken out of service.
3. Follow appropriate safe work procedures when handling or disturbing asbestos, lead, mercury and silica.

Please refer to Section 4.0 of this report for detailed recommendations regarding administrative and remedial actions.

This Executive Summary is subject to the same standard limitations as contained in the report and must be read in conjunction with the entire report.



Designated Substances Survey Report

32 Division
30 Ellerslie Ave., Toronto, ON
The City of Toronto

December 4, 2015

Pinchin File: 103037

FINAL

TABLE OF CONTENTS

1.0	INTRODUCTION AND SCOPE	1
1.1	Scope of Survey	1
2.0	BACKGROUND INFORMATION	2
2.1	Building Description	2
3.0	FINDINGS	2
3.1	Asbestos	2
3.2	Lead	7
3.3	Silica	8
3.4	Mercury	8
3.5	Polychlorinated Biphenyls	8
3.6	Mould	9
4.0	RECOMMENDATIONS	9
4.1	General	9
4.2	On-going Management and Maintenance	9
5.0	LIMITATIONS	10
6.0	REFERENCES	10

APPENDICES

APPENDIX I	Drawings
APPENDIX II-A	Asbestos Analytical Certificates
APPENDIX II-B	Lead Analytical Certificates
APPENDIX II-C	PCB Analytical Certificates
(No Information to Report)	
APPENDIX III	Methodology
APPENDIX IV	Photographs
APPENDIX V	Survey Form



1.0 INTRODUCTION AND SCOPE

The City of Toronto (Client) retained Pinchin Ltd. (Pinchin) to conduct a Designated Substances Survey of the Police Services 32 Division, located at 30 Ellerslie Ave., Toronto, ON.

The survey was performed by John Edwards, B.A., PCEM, Senior Project Technologist on June 4, 2015.

The surveyor was accompanied by a representative from the City of Toronto during the survey. The building was occupied at the time of the survey.

The objective of the survey was to document the locations of specified Designated Substances, polychlorinated biphenyls (PCBs) and mould, evaluate their condition, and develop corrective action plans as required. This survey is only to be used for the purposes of long term management and routine maintenance. The results of this survey are not to be used for construction, renovation, demolition or project tendering purposes.

1.1 Scope of Survey

The survey was performed to review the location and type of specified hazardous building materials present in the building.

For the purpose of the survey and this report, hazardous building materials include the following Designated Substances:

- Asbestos
- Lead
- Silica
- Mercury

The survey also included:

- Polychlorinated Biphenyls (PCBs)
- Mould

The following Ontario Designated Substances are not typically found in building materials in a composition/state that is hazardous and were not included in this survey:

- Arsenic
- Acrylonitrile
- Benzene
- Coke oven emissions



Designated Substances Survey Report

32 Division
30 Ellerslie Ave., Toronto, ON
The City of Toronto

December 4, 2015

Pinchin File: 103037

FINAL

- Ethylene oxide
- Isocyanates
- Vinyl chloride monomer

2.0 BACKGROUND INFORMATION

2.1 Building Description

Item	Details
Building Use	Police Station
Number of Floors/Levels	2 stories plus 1 below grade
Total Area of Building (Square Feet)	15,000
Year of Construction	1978
Structure	Structural steel, concrete
Exterior Cladding	Brick
HVAC	Rooftop units
Roof	Built-up roofing
Flooring	Vinyl tile, terrazzo, carpet, ceramic tiles, concrete
Interior Walls	Drywall, concrete block, plaster
Ceilings	Drywall, plaster, acoustic ceiling tiles

3.0 FINDINGS

3.1 Asbestos

3.1.1 Suspect Building Materials Not Found

The following types of building materials may historically contain asbestos but were not observed in the building and are not discussed in the report findings:

- Asbestos cement products
- Vinyl sheet flooring
- Firestopping

3.1.2 *Spray-Applied Fireproofing and Thermal Insulation*

In 1998 T. Harris, and in 2006 ECOH Management Inc. reported the presence of sprayed fireproofing in Location B-075. The three samples collected by others were found not to contain asbestos.

Texture Finishes (Acoustic/Decorative)

Texture finish, present on drywall ceilings on the first floor, was previously sampled (1998, 2006) and found not to contain asbestos.




Non-asbestos texture finish

3.1.3 *Thermal Systems Insulation (TSI)*

3.1.3.1 *Pipe Insulation*

Parging cement, previously sampled (1998) and found to contain chrysotile asbestos, is present on pipe fittings (elbows, valves, tees, hangers etc.) on the hot water heating systems. Parging cement is a friable insulation, jacketed with canvas and is in good condition. Refer to the Survey Form in Appendix V for locations, quantities and condition of asbestos-containing parging cement.

Non-asbestos insulation (e.g. fibreglass) is present on pipes throughout the assessed area.



Asbestos-containing parging cement

3.1.3.2 Duct Insulation

Ducts are either uninsulated or insulated with non-asbestos fibreglass and jacketed with either canvas or foil.



Non-asbestos fibreglass duct insulation

3.1.3.3 Mechanical Equipment Insulation

Mechanical equipment is either not insulated or insulated with non-asbestos fibreglass



Fibreglass insulation on tank



Un-insulated equipment

3.1.4 Acoustic Ceiling Tiles

Three distinct types of non-asbestos acoustic ceiling tile are present, as follows:

Size, Type, Pattern	Sample Number or Date Code	Asbestos Type
ACT01: 24"x48", lay-in, width wise fissure and pinhole	11087-B42-01 & 02 and sample 1998 - 4	None detected
ACT02: 24"x48", lay-in, random pinhole pattern	2015-A0004A-C	None detected
ACT03: 24"x48", lay-in, random fleck and hole	2015-A0006A-C	None detected



ACT01



ACT02

Refer to additional photographs in Appendix IV.

3.1.5 Plaster

Plaster is present on walls and ceilings throughout the building. Plaster was in good condition and therefore, not sampled. Plaster is assumed to contain asbestos. Plaster is non-friable in place, but generates friable dust upon removal. Refer to the Survey Form in Appendix V for locations of plaster.

3.1.6 Drywall Joint Compound


Drywall (gypsum board) and drywall joint compound is present as a wall and ceiling finish throughout the building. Drywall joint compound was in good condition and therefore, not sampled. Drywall joint compound is assumed to contain asbestos. Joint compound is non-friable in place, but generates friable dust upon removal. Refer to the Survey Form in Appendix V for locations of drywall joint compound.

3.1.7 Vinyl Floor Tile and Mastic


Vinyl floor tiles and mastic are present as follows:

Size, Pattern, Colour	Sample Number	Asbestos Type (tile)	Asbestos Type (mastic)
VFT01: 12"x12" beige with black and white streaks, black mastic	2015-A0001A-C	None detected	None detected
VFT02: 12"x12" white with beige and brown smears, black mastic	2015-A0002A-C	None detected	None detected
VFT03: 12"x12" black, yellow mastic	2015-A0003A-C	None detected	None detected
VFT04: 12"x12" off white with white and black streaks, yellow mastic	2015-A0005A-C	None detected	None detected

Size, Pattern, Colour	Sample Number	Asbestos Type (tile)	Asbestos Type (mastic)
VFT05: 12"x12" blue with white smears, black mastic	2015-A0007A-C	None detected	None detected
VFT06: 12"x12" beige and brown smears, yellow mastic	2015-A0008A-C	None detected	None detected



VFT01



VFT02

Refer to additional photographs in Appendix IV.

3.1.8 Assumed Asbestos Materials

A number of materials which might contain asbestos were not sampled during our survey due to limitations in scope and methodology. Where present, these materials must be assumed to be an asbestos material and are best sampled during project planning and preparation of contract documents for their removal. Materials assumed to contain asbestos include:

- roofing, felts and tar
- concrete floor levelling compound
- elevator and lift brakes
- electrical components or wiring within control centers, breakers, motors or lights, insulation on wiring
- vermiculite in concrete block wall cavities
- adhesives and duct mastics
- sealants, caulking and putty
- mechanical packing, ropes and gaskets
- fire resistant doors

3.2 Lead

3.2.1 Paints

One paint chip sample was collected from an interior painted finish in poor condition, and found to contain less than the City of Toronto action level of 0.1% lead. All other paints were in good condition (i.e. not flaking, peeling or delaminating). Paints not sampled are assumed to contain lead. Appendix II-B presents the analytical results.

The following table summarizes the sample analytical result and the sampling location.


Sample Number	Colour, Substrate Description	Location	Lead (%)
2015-L001	Grey on concrete floor	B-004 – Mechanical Room	0.084



Grey paint on concrete floor

3.2.2 Lead Products and Applications

Lead-containing batteries may be present in emergency lighting.



Battery operated emergency

3.2.3 Assumed Lead Materials

Lead may be present in a number of materials which were not assessed and/or sampled. The following materials, where found, should be considered to contain lead.

- electrical components, including wiring connectors, fibre optic cable sheathing, grounding conductors, and solder

3.3 Silica

Crystalline silica is assumed component of the following building materials where present in the building:

- poured or pre-cast concrete
- masonry and mortar
- ceramic tiles, grout
- plaster


3.4 Mercury

3.4.1 Lamps

Mercury vapour is present in fluorescent lamps.

3.4.2 Mercury-Containing Devices

Mercury is present as a liquid in thermostats found in Location 2-102.



Mercury-containing thermostat

3.5 Polychlorinated Biphenyls

3.5.1 Lighting Ballasts

The building has not been comprehensively re-lamped with new energy efficient light ballasts and lamps, and as such, a percentage of light ballasts may be pre-1980 and contain PCBs.



3.5.2 Transformers

Transformers were not found during the survey.

3.6 Mould

Visible mould growth was not found in the assessed area.

4.0 RECOMMENDATIONS

4.1 General

Perform a detailed intrusive survey prior to building renovation or demolition operations. The survey should include; destructive testing (i.e. coring and/or removal of building finishes and components), and sampling of materials not previously tested (i.e. roofing materials, caulking, mastics).

4.2 On-going Management and Maintenance

The following recommendations are made regarding on-going management and maintenance work involving the hazardous materials identified.

4.2.1 Asbestos

Perform an assessment of asbestos materials on an annual basis. The next assessment of ACM should be performed prior to June 2016 to remain in compliance.

Remove all asbestos-containing materials (ACM) prior to alteration or maintenance work or if ACM may be disturbed by the work. Follow appropriate asbestos precautions for the classification of work being performed.

Update the asbestos inventory report upon completion of any abatement and removal of asbestos-containing materials.

4.2.2 Lead

Disturbance of lead in paint and coatings (or other materials) during maintenance activities may result in over-exposure to lead dust or fumes. The need for work procedures, engineering controls and personal protective equipment will need to be assessed on a project-by-project basis and must comply with provincial standards or guidelines. Performing an exposure assessment during work that disturbs lead in paints and coatings may be able to alleviate the use of some of the precautions specified by these standards or guidelines.

Lead-containing items (lead-acid batteries) should be recycled when taken out of service.



4.2.3 Silica

Disturbance of silica-containing products during maintenance activities may result in excessive exposures to airborne silica, especially if performed indoors and dry. Cutting, grinding, drilling or demolition of materials containing silica should be completed only with proper respiratory protection and other worker safety precautions that comply with provincial standards or guidelines.

4.2.4 Mercury

Recycle and reclaim mercury from fluorescent light tubes and thermostats when taken out of service. Do not break lamps or separate liquid mercury from components. Light tubes are accepted free of charge at many local recycling depots. Liquid mercury is classified as a hazardous waste and must be disposed of in accordance with local regulations.

4.2.5 PCBs

When light fixtures are removed from service, examine light ballasts for PCB content. If ballasts are not clearly labelled as "non-PCB", or are suspected to contain PCBs; package and ship ballasts for destruction at a federally permitted facility.

Dispose of non-liquid PCB materials when they are removed from the building.

5.0 LIMITATIONS

The work performed by Pinchin was conducted in accordance with the City of Toronto Contract Number 47018468, effective July 31, 2014.

6.0 REFERENCES

The following legislation and documents were referenced in completing the survey and this report:

1. Asbestos on Construction Projects and in Buildings and Repair Operations, Ontario Regulation 278/05.
2. Designated Substances, Ontario Regulation 490/09.
3. Lead on Construction Projects, Ministry of Labour Guidance Document.
4. Ministry of the Environment Regulation, R.R.O. 1990 Reg. 347 as amended.
5. Surface Coating Materials Regulations, SOR/2005-109, Hazardous Products Act.
6. Silica on Construction Projects, Ministry of Labour Guidance Document.
7. Alert – Mould in Workplace Buildings, Ontario Ministry of Labour.



Designated Substances Survey Report

32 Division
30 Eglerslie Ave., Toronto, ON
The City of Toronto

December 4, 2015

Pinchin File: 103037


FINAL

8. Standard Operating Procedures for Designated Substance Surveys, dated April, 2014,
City of Toronto, Facilities Management.

\\pinchin.com\miss\Job\103000s\103037 CITYOFTORONTO,VariousLocati,DSUB,ASSMT\Toronto Police Services\30 Eglerslie Avenue\Report\FINAL\30 Eglerslie Ave_DSS_2015.docx

Template: Master Report for Hazardous Materials Assessment Report (Tablet Management), Haz, December 10, 2014

APPENDIX I
Drawings



ALL PLASTER AND DRYWALL JOINT COMPOUND
ARE ASSUMED TO CONTAIN ASBESTOS.

LEGEND:

- 1-01 LOCATION NUMBER
- NAR NO ACCESS TO ROOM
- ⊙ ASBESTOS BULK SAMPLE
- △ PAINT (LEAD) BULK SAMPLE
- CONFIRMED AND/OR ASSUMED
ASBESTOS-CONTAINING MATERIAL
- M MERCURY (THERMOSTAT)

NOT ALL KNOWN OR ASSUMED DESIGNATED
SUBSTANCES ARE IDENTIFIED ON THE
DRAWING. REFER TO THE DESIGNATED
SUBSTANCE REPORT FOR A COMPLETE LIST
OF KNOWN AND ASSUMED DESIGNATED
SUBSTANCES.

CLIENT:

CITY OF TORONTO

LOCATION:

32 DIVISION
30 ELLERSLIE AVENUE
TORONTO, ONTARIO

TITLE:

DESIGNATED SUBSTANCES
SURVEY
BASEMENT

DATE:

2015/06/04

PROJECT # :

103037

DRAWN BY:

HB

DRAWING:

CHECKED BY:

JE

SCALE:

NTS

1 OF 3



LEGEND:

- 1-01 LOCATION NUMBER
- NAR NO ACCESS TO ROOM
- ASBESTOS BULK SAMPLE
- PAINT (LEAD) BULK SAMPLE
- CONFIRMED AND/OR ASSUMED ASBESTOS-CONTAINING MATERIAL
- M MERCURY (THERMOSTAT)

NOT ALL KNOWN OR ASSUMED DESIGNATED SUBSTANCES ARE IDENTIFIED ON THE DRAWING. REFER TO THE DESIGNATED SUBSTANCE REPORT FOR A COMPLETE LIST OF KNOWN AND ASSUMED DESIGNATED SUBSTANCES.

CLIENT:

CITY OF TORONTO

LOCATION:

32 DIVISION
30 ELLERSLIE AVENUE
TORONTO, ONTARIO

TITLE:

DESIGNATED SUBSTANCES
SURVEY
GROUND FLOOR

DATE:

2015/06/04

PROJECT # :

103037

DRAWN BY:

HB

DRAWING:


CHECKED BY:

JE

SCALE:

NTS

2 OF 3



ALL PLASTER AND DRYWALL JOINT COMPOUND
ARE ASSUMED TO CONTAIN ASBESTOS.



LEGEND:

- 1-01 LOCATION NUMBER
- NAR NO ACCESS TO ROOM
- ASBESTOS BULK SAMPLE
- PAINT (LEAD) BULK SAMPLE
- CONFIRMED AND/OR ASSUMED ASBESTOS-CONTAINING MATERIAL
- M MERCURY (THERMOSTAT)

NOT ALL KNOWN OR ASSUMED DESIGNATED SUBSTANCES ARE IDENTIFIED ON THE DRAWING. REFER TO THE DESIGNATED SUBSTANCE REPORT FOR A COMPLETE LIST OF KNOWN AND ASSUMED DESIGNATED SUBSTANCES.

CLIENT:

CITY OF TORONTO

LOCATION:

32 DIVISION
30 ELLERSLIE AVENUE
TORONTO, ONTARIO

TITLE:

DESIGNATED SUBSTANCES
SURVEY
SECOND FLOOR

DATE:

2015/06/04

PROJECT # :

103037

DRAWN BY:

HB

DRAWING:


CHECKED BY:

JE

SCALE:

NTS

3 OF 3



ALL PLASTER AND DRYWALL JOINT COMPOUND
ARE ASSUMED TO CONTAIN ASBESTOS.

APPENDIX II-A
Asbestos Analytical Certificates



Bulk Asbestos Analysis

By Polarized Light Microscopy
EPA Method: 600/R-93/116 and 600/M4-82-020



NVLAP Lab Code: 200664-0

Customer: Pinchin Ltd.
50 Wellington Street East
Suite 200
Toronto ON M5E 1C8

Attn: John Edwards
Juliette McIntyre

Lab Order ID: 1510997
Analysis ID: 1510997_PLM
Date Received: 6/8/2015
Date Reported: 6/12/2015

Project: City of Toronto, 30 Ellerslie Ave., Toronto

Sample ID	Description	Asbestos	Fibrous Components	Non-Fibrous Components	Attributes
Lab Sample ID	Lab Notes				Treatment
2015-A0001A - A	VFT01 - Vinyl floor tile, 12"x12", beige with black and white streaks and bck masticl,	None Detected		100% Other	Beige Non Fibrous Heterogeneous
1510997PLM_1	tile				Dissolved
2015-A0001A - B	VFT01 - Vinyl floor tile, 12"x12", beige with black and white streaks and bck masticl,	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_25	mastic				Dissolved
2015-A0001B - A	VFT01 - Vinyl floor tile, 12"x12", beige with black and white streaks and black mastic	None Detected		100% Other	Beige Non Fibrous Heterogeneous
1510997PLM_2	tile				Dissolved
2015-A0001B - B	VFT01 - Vinyl floor tile, 12"x12", beige with black and white streaks and black mastic	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_26	mastic				Dissolved
2015-A0001C - A	VFT01 - Vinyl floor tile, 12"x12", beige with black and white streaks and black mastic	None Detected		100% Other	Beige Non Fibrous Heterogeneous
1510997PLM_3	tile - ashed				Ashed
2015-A0001C - B	VFT01 - Vinyl floor tile, 12"x12", beige with black and white streaks and black mastic	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_27	mastic				Dissolved
2015-A0002A - A	VFT02 - Vinyl floor tile, 12"x12" white with beige and brown smears and black masti	None Detected		100% Other	Beige Non Fibrous Heterogeneous
1510997PLM_4	tile				Dissolved
2015-A0002A - B	VFT02 - Vinyl floor tile, 12"x12" white with beige and brown smears and black masti	None Detected		100% Other	Black, Yellow Non Fibrous Heterogeneous
1510997PLM_28	mixed mastic				Dissolved

Disclaimer: Due to the nature of the EPA 600 method, asbestos may not be detected in samples containing low levels of asbestos. We strongly recommended that analysis of floor tiles, vermiculite, and/or heterogeneous soil samples be conducted by TEM for confirmation of "None Detected" by PLM. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government. Estimated MDL is 0.1%.

Charmel Dozier (42)

Analyst

Approved Signatory



Bulk Asbestos Analysis

By Polarized Light Microscopy
EPA Method: 600/R-93/116 and 600/M4-82-020



NVLAP Lab Code: 200664-0

Customer: Pinchin Ltd.
50 Wellington Street East
Suite 200
Toronto ON M5E 1C8

Attn: John Edwards
Juliette McIntyre

Lab Order ID: 1510997
Analysis ID: 1510997_PLM
Date Received: 6/8/2015
Date Reported: 6/12/2015

Project: City of Toronto, 30 Ellerslie Ave., Toronto

Sample ID	Description	Asbestos	Fibrous Components	Non-Fibrous Components	Attributes
Lab Sample ID	Lab Notes				Treatment
2015-A0002B - A	VFT02 - Vinyl floor tile, 12"x12" white with beige and brown smears and black masti	None Detected		100% Other	Beige Non Fibrous Heterogeneous
1510997PLM_5	tile				Dissolved
2015-A0002B - B	VFT02 - Vinyl floor tile, 12"x12" white with beige and brown smears and black masti	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_29	mastic				Dissolved
2015-A0002C - A	VFT02 - Vinyl floor tile, 12"x12" white with beige and brown smears and black masti	None Detected		100% Other	Beige Non Fibrous Heterogeneous
1510997PLM_6	tile - ashed				Ashed
2015-A0002C - B	VFT02 - Vinyl floor tile, 12"x12" white with beige and brown smears and black masti	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_30	mastic				Dissolved
2015-A0003A - A	VFT03 - Vinyl floor tile, 12"x12" black, yellow mastic, Location B-30	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_7	tile				Dissolved
2015-A0003A - B	VFT03 - Vinyl floor tile, 12"x12" black, yellow mastic, Location B-30	None Detected		100% Other	Tan Non Fibrous Heterogeneous
1510997PLM_31	mastic				Dissolved
2015-A0003B - A	VFT03 - Vinyl floor tile, 12"x12" black, yellow mastic, Location B-30	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_8	tile				Dissolved
2015-A0003B - B	VFT03 - Vinyl floor tile, 12"x12" black, yellow mastic, Location B-30	None Detected		100% Other	Tan Non Fibrous Heterogeneous
1510997PLM_32	mastic				Dissolved

Disclaimer: Due to the nature of the EPA 600 method, asbestos may not be detected in samples containing low levels of asbestos. We strongly recommend that analysis of floor tiles, vermiculite, and/or heterogeneous soil samples be conducted by TEM for confirmation of "None Detected" by PLM. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government. Estimated MDL is 0.1%.

Charmel Dozier (42)

Analyst

Approved Signatory



Bulk Asbestos Analysis

By Polarized Light Microscopy
EPA Method: 600/R-93/116 and 600/M4-82-020



NVLAP Lab Code: 200664-0

Customer: Pinchin Ltd.
50 Wellington Street East
Suite 200
Toronto ON M5E 1C8

Attn: John Edwards
Juliette McIntyre

Lab Order ID: 1510997
Analysis ID: 1510997_PLM
Date Received: 6/8/2015
Date Reported: 6/12/2015

Project: City of Toronto, 30 Ellerslie Ave., Toronto

Sample ID	Description	Asbestos	Fibrous Components	Non-Fibrous Components	Attributes
Lab Sample ID	Lab Notes				Treatment
2015-A0003C - A	VFT03 - Vinyl floor tile, 12"x12" black, yellow mastic, Location B-30	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_9	tile - ashed				Ashed
2015-A0003C - B	VFT03 - Vinyl floor tile, 12"x12" black, yellow mastic, Location B-30	None Detected		100% Other	Tan Non Fibrous Heterogeneous
1510997PLM_33	mastic				Dissolved
2015-A0004A	ACT02 - Acoustic ceiling tile, 24"x48" random hole pattern, Location B-39	None Detected	40% Cellulose 40% Mineral Wool	10% Perlite 10% Other	Tan Fibrous Heterogeneous
1510997PLM_10					Teased
2015-A0004B	ACT02 - Acoustic ceiling tile, 24"x48" random hole pattern, Location B-39	None Detected	40% Cellulose 40% Mineral Wool	10% Perlite 10% Other	Tan Fibrous Heterogeneous
1510997PLM_11					Teased
2015-A0004C	ACT02 - Acoustic ceiling tile, 24"x48" random hole pattern, Location B-39	None Detected	40% Cellulose 40% Mineral Wool	10% Perlite 10% Other	Tan Fibrous Heterogeneous
1510997PLM_12					Teased
2015-A0005A - A	VFT04 - Vinyl floor tile, 12"x12", off-white with white and black streaks & yellow ma	None Detected		100% Other	Cream Non Fibrous Heterogeneous
1510997PLM_13	tile				Dissolved
2015-A0005A - B	VFT04 - Vinyl floor tile, 12"x12", off-white with white and black streaks & yellow ma	None Detected		100% Other	Yellow Non Fibrous Heterogeneous
1510997PLM_34	mastic				Dissolved, Teased
2015-A0005B - A	VFT04 - Vinyl floor tile, 12"x12", off-white with white and black streaks & yellow ma	None Detected		100% Other	Cream Non Fibrous Heterogeneous
1510997PLM_14	tile				Dissolved

Disclaimer: Due to the nature of the EPA 600 method, asbestos may not be detected in samples containing low levels of asbestos. We strongly recommend that analysis of floor tiles, vermiculite, and/or heterogeneous soil samples be conducted by TEM for confirmation of "None Detected" by PLM. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government. Estimated MDL is 0.1%.

Charmel Dozier (42)

Analyst

Approved Signatory



Bulk Asbestos Analysis

By Polarized Light Microscopy
EPA Method: 600/R-93/116 and 600/M4-82-020



NVLAP Lab Code: 200664-0

Customer: Pinchin Ltd.
50 Wellington Street East
Suite 200
Toronto ON M5E 1C8

Attn: John Edwards
Juliette McIntyre

Lab Order ID: 1510997
Analysis ID: 1510997_PLM
Date Received: 6/8/2015
Date Reported: 6/12/2015

Project: City of Toronto, 30 Ellerslie Ave., Toronto

Sample ID	Description	Asbestos	Fibrous Components	Non-Fibrous Components	Attributes
Lab Sample ID	Lab Notes				Treatment
2015-A0005B - B	VFT04 - Vinyl floor tile, 12"x12", off-white with white and black streaks & yellow ma	None Detected		100% Other	Yellow Non Fibrous Heterogeneous
1510997PLM_35	mastic				Dissolved
2015-A0005C - A	VFT04 - Vinyl floor tile, 12"x12", off-white with white and black streaks & yellow ma	None Detected		100% Other	Cream Non Fibrous Heterogeneous
1510997PLM_15	tile - ashed				Dissolved
2015-A0005C - B	VFT04 - Vinyl floor tile, 12"x12", off-white with white and black streaks & yellow ma	None Detected		100% Other	Yellow Non Fibrous Heterogeneous
1510997PLM_36	mastic				Dissolved
2015-A0006A	ACT03 - Acoustic ceiling tile, 24"x48", random fleck and hole, Location 2-110	None Detected	40% Cellulose 40% Mineral Wool	10% Perlite 10% Other	Tan Fibrous Heterogeneous
1510997PLM_16					Teased
2015-A0006B	ACT03 - Acoustic ceiling tile, 24"x48", random fleck and hole, Location 2-110	None Detected	40% Cellulose 40% Mineral Wool	10% Perlite 10% Other	Tan Fibrous Heterogeneous
1510997PLM_17					Teased
2015-A0006C	ACT03 - Acoustic ceiling tile, 24"x48", random fleck and hole, Location 2-110	None Detected	40% Cellulose 40% Mineral Wool	10% Perlite 10% Other	Tan Fibrous Heterogeneous
1510997PLM_18					Teased
2015-A0007A - A	VFT05 - Vinyl floor tile, 12"x12", blue with white smears & black mastic, Locati	None Detected		100% Other	Blue Non Fibrous Heterogeneous
1510997PLM_19	tile				Dissolved
2015-A0007A - B	VFT05 - Vinyl floor tile, 12"x12", blue with white smears & black mastic, Locati	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_37	mastic				Dissolved

Disclaimer: Due to the nature of the EPA 600 method, asbestos may not be detected in samples containing low levels of asbestos. We strongly recommend that analysis of floor tiles, vermiculite, and/or heterogeneous soil samples be conducted by TEM for confirmation of "None Detected" by PLM. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government. Estimated MDL is 0.1%.

Charmel Dozier (42)

Analyst

Approved Signatory



Bulk Asbestos Analysis

By Polarized Light Microscopy
EPA Method: 600/R-93/116 and 600/M4-82-020



NVLAP Lab Code: 200664-0

Customer: Pinchin Ltd.
50 Wellington Street East
Suite 200
Toronto ON M5E 1C8

Attn: John Edwards
Juliette McIntyre

Lab Order ID: 1510997
Analysis ID: 1510997_PLM
Date Received: 6/8/2015
Date Reported: 6/12/2015

Project: City of Toronto, 30 Ellerslie Ave., Toronto

Sample ID	Description	Asbestos	Fibrous Components	Non-Fibrous Components	Attributes
Lab Sample ID	Lab Notes				Treatment
2015-A0007B - A	VFT05 - Vinyl floor tile, 12"x12", blue with white smears & black mastic, Locati	None Detected		100% Other	Blue Non Fibrous Heterogeneous
1510997PLM_20	tile				Dissolved
2015-A0007B - B	VFT05 - Vinyl floor tile, 12"x12", blue with white smears & black mastic, Locati	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_38	mastic				Dissolved
2015-A0007C - A	VFT05 - Vinyl floor tile, 12"x12", blue with white smears & black mastic, Locati	None Detected		100% Other	Blue Non Fibrous Heterogeneous
1510997PLM_21	tile - ashed				Ashed
2015-A0007C - B	VFT05 - Vinyl floor tile, 12"x12", blue with white smears & black mastic, Locati	None Detected		100% Other	Black Non Fibrous Heterogeneous
1510997PLM_39	mastic				Dissolved
2015-A0008A - A	VFT06 - Vinyl floor tile, 12"x12", beige with brown smears, yellow mastic, Locatio	None Detected		100% Other	Beige Non Fibrous Heterogeneous
1510997PLM_22	tile				Dissolved
2015-A0008A - B	VFT06 - Vinyl floor tile, 12"x12", beige with brown smears, yellow mastic, Locatio	None Detected		100% Other	Yellow Non Fibrous Heterogeneous
1510997PLM_40	mastic				Dissolved
2015-A0008B - A	VFT06 - Vinyl floor tile, 12"x12", beige with brown smears, yellow mastic, Locatio	None Detected		100% Other	Beige Non Fibrous Heterogeneous
1510997PLM_23	tile				Dissolved
2015-A0008B - B	VFT06 - Vinyl floor tile, 12"x12", beige with brown smears, yellow mastic, Locatio	None Detected		100% Other	Yellow Non Fibrous Heterogeneous
1510997PLM_41	mastic				Dissolved

Disclaimer: Due to the nature of the EPA 600 method, asbestos may not be detected in samples containing low levels of asbestos. We strongly recommend that analysis of floor tiles, vermiculite, and/or heterogeneous soil samples be conducted by TEM for confirmation of "None Detected" by PLM. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government. Estimated MDL is 0.1%.

Charmel Dozier (42)

Analyst

Approved Signatory



Bulk Asbestos Analysis

By Polarized Light Microscopy
EPA Method: 600/R-93/116 and 600/M4-82-020



NVLAP Lab Code: 200664-0

Customer: Pinchin Ltd.
50 Wellington Street East
Suite 200
Toronto ON M5E 1C8

Attn: John Edwards
Juliette McIntyre

Lab Order ID: 1510997
Analysis ID: 1510997_PLM
Date Received: 6/8/2015
Date Reported: 6/12/2015

Project: City of Toronto, 30 Ellerslie Ave., Toronto

Sample ID	Description	Asbestos	Fibrous Components	Non-Fibrous Components	Attributes
Lab Sample ID	Lab Notes				Treatment
2015-A0008C - A	VFT06 - Vinyl floor tile, 12"x12", beige with brown smears, yellow mastic, Locatio	None Detected		100% Other	Beige Non Fibrous Heterogeneous
1510997PLM_24	tile - ashed				Dissolved
2015-A0008C - B	VFT06 - Vinyl floor tile, 12"x12", beige with brown smears, yellow mastic, Locatio	None Detected		100% Other	Yellow Non Fibrous Heterogeneous
1510997PLM_42	mastic				Dissolved

Disclaimer: Due to the nature of the EPA 600 method, asbestos may not be detected in samples containing low levels of asbestos. We strongly recommended that analysis of floor tiles, vermiculite, and/or heterogeneous soil samples be conducted by TEM for confirmation of "None Detected" by PLM. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government. Estimated MDL is 0.1%.

Charmel Dozier (42)

Analyst

Approved Signatory

Client: Pinchin Ltd.
Contact: John Edwards / Juliette McIntyre
 50 Wellington Street East, Suite
 200, Toronto, ON M5E 1C8
Address: 416-368-6555
Phone: 416-368-4120
Fax: jedwards@pinchin.com
Email: jmcintyre@pinchin.com
 City of Toronto, 30 Eglerslie Ave.,
 Toronto
Project:
Client Notes:
P.O. #: 103037
Date Submitted: June 5th 2015
Analysis: PLM - Stop Positive
TurnAroundTime: 4 days

***Instructions:**
Use Column "B" for your contact info

To See an Example Click the
bottom Example Tab.

Enter samples between "<<" and ">>"

Begin Samples with a "<<" above the first sample
and end with a ">>" below the last sample.
Only Enter your data on the first sheet "Sheet 1"

Note: Data 1 and Data 2 are optional
fields that do not show up on the official
report, however they will be included
in the electronic data returned to you
to facilitate your reintegration of the report data.

Version 1-15-2012

Invoice to:

Contact name here
Email address here

Scientific
Analytical
Institute



4604 Dundas Dr.
Greensboro, NC 27407
Phone: 336.292.3888
Email: 336.292.3313
lab.com

1510997

Sample Number	Data 1 (Lab use only)	Sample Description	Data 2 (Lab use only)
<<			
2015-A0001A		VFT01 - Vinyl floor tile, 12"x12", beige with black and white streaks and bck mastici, Location B-06	
2015-A0001B		VFT01 - Vinyl floor tile, 12"x12", beige with black and white streaks and black mastic, Location B-17	
2015-A0001C		VFT01 - Vinyl floor tile, 12"x12", beige with black and white streaks and black mastic, Location 1-66	
2015-A0002A		VFT02 - Vinyl floor tile, 12"x12" white with beige and brown smears and black mastic, Location B-15	
2015-A0002B		VFT02 - Vinyl floor tile, 12"x12" white with beige and brown smears and black mastic, Location B-15	
2015-A0002C		VFT02 - Vinyl floor tile, 12"x12" white with beige and brown smears and black mastic, Location B-15	
2015-A0003A		VFT03 - Vinyl floor tile, 12"x12" black, yellow mastic, Location B-30	
2015-A0003B		VFT03 - Vinyl floor tile, 12"x12" black, yellow mastic, Location B-30	
2015-A0003C		VFT03 - Vinyl floor tile, 12"x12" black, yellow mastic, Location B-30	
2015-A0004A		ACT02 - Acoustic ceiling tile, 24"x48" random hole pattern, Location B-39	
2015-A0004B		ACT02 - Acoustic ceiling tile, 24"x48" random hole pattern, Location B-39	
2015-A0004C		ACT02 - Acoustic ceiling tile, 24"x48" random hole pattern, Location B-39	
2015-A0005A		VFT04 - Vinyl floor tile, 12"x12", off-white with white and black streaks & yellow mastic, Location 1-63	
2015-A0005B		VFT04 - Vinyl floor tile, 12"x12", off-white with white and black streaks & yellow mastic, Location 1-65	
2015-A0005C		VFT04 - Vinyl floor tile, 12"x12", off-white with white and black streaks & yellow mastic, Location 1-67	
2015-A0006A		ACT03 - Acoustic ceiling tile, 24"x48", random fleck and hole, Location 2-110	
2015-A0006B		ACT03 - Acoustic ceiling tile, 24"x48", random fleck and hole, Location 2-110	
2015-A0006C		VFT05 - Vinyl floor tile, 12"x12", blue with white smears & black mastic, Location 2-113	
2015-A0007A		VFT05 - Vinyl floor tile, 12"x12", blue with white smears & black mastic, Location 2-114	
2015-A0007B		VFT05 - Vinyl floor tile, 12"x12", blue with white smears & black mastic, Location 2-113	
2015-A0007C		VFT06 - Vinyl floor tile, 12"x12", beige with brown smears, yellow mastic, Location 2-107	
2015-A0008A		VFT06 - Vinyl floor tile, 12"x12", beige with brown smears, yellow mastic, Location 2-109	
2015-A0008B		VFT06 - Vinyl floor tile, 12"x12", beige with brown smears, yellow mastic, Location 2-116	
2015-A0008C			
>>			

Accepted ☒

Rejected ☐

M. Irving
68 10 am

APPENDIX II-B
Lead Analytical Certificates



Analysis for Lead Concentration in Paint Chips

by Flame Atomic Absorption Spectroscopy
EPA SW-846 3050B/6010C/7420



Customer: Pinchin Ltd.
2470 Milltower Court
Mississauga ON L5N 7W5

Attn: John Edwards
Juliette McIntyre

Lab Order ID: 1511001
Analysis ID: 1511001_PBP
Date Received: 6/8/2015
Date Reported: 6/15/2015

Project: 30 Ellerslie Ave.

Sample ID	Description	Mass (g)	Concentration (ppm)	Concentration (% by weight)
Lab Sample ID	Lab Notes			
2015-L001	Grey paint on concrete floor, location B-04	0.0491	840	0.084%
1511001PBP_1				

Unless otherwise noted blank sample correction was not performed on analytical results. Scientific Analytical Institute participates in the AIHA IHPAT program. IHPAT Laboratory ID: 173190. This report relates only to the samples tested and may not be reproduced, except in full, without the written approval of SAI. Analytical uncertainty available upon request. The quality control samples run with the samples in this report have passed all EPA required specifications unless otherwise noted. RL: (Report Limit for an undiluted 50ml sample is 4µg Total Pb).

Melissa Sharps (1)

Analyst

Scientific Analytical Institute, Inc. 4604 Dundas Dr. Greensboro, NC 27407 (336) 292-3888

Laboratory Director

APPENDIX II-C
PCB Analytical Certificates
(No Information to Report)

APPENDIX III
Methodology



1.0 GENERAL

The following survey methodology is based on the requirements of the *Standard Operation Procedure for Designated Substance Surveys*, dated April, 2014, provided by the City of Toronto (the "SOP").

Pinchin conducted a room-by-room survey (rooms, corridors, service areas, exterior, etc.) to identify the hazardous building materials as defined in Section 1.1. Information regarding the approximate quantity, location, and condition of hazardous building materials encountered and visually estimated quantities were recorded on the *Survey Form*, provided by the City of Toronto, found in Appendix V. The locations of any samples collected were recorded on small-scale plans, found in Appendix I.

Drawings (i.e., floor plans), previous reports, and Survey Forms, were referenced where provided.

1.1 Limitations on Scope

The survey excludes the following:

- Owner or occupant articles (e.g. stored items, furniture, appliances, etc.);
- Underground materials or equipment (e.g. vessels, drums, underground storage tanks, pipes, etc.);
- Building envelope, structural components, inaccessible or concealed materials or other items where sampling may cause consequential damage to the property.
- Energized systems (e.g. internal boiler components, elevators, mechanical or electrical components);
- Controlled products (e.g. stored chemicals, operational or process-related substances); and
- Materials not typically associated with construction (e.g. settled dust, spills, residual contamination from prior spills, etc.).

The survey was limited to non-intrusive testing. Concealed spaces such as those above solid ceilings and within shafts and pipe chases were accessed via existing access panels only. Pinchin did not conduct demolition of walls, solid ceilings, structural items, interior finishes or exterior building finishes, to determine the presence of concealed materials.

1.2 Asbestos

Pinchin conducted an inspection for the presence of friable and non-friable asbestos-containing materials (ACM). A friable material is a material that when dry can be crumbled, pulverized or powdered by hand pressure.



Pinchin collected samples at a rate that is in compliance with Table 1 of O.Reg. 278/05. A separate set of samples was collected of each of homogenous material sampled. A homogenous material is defined by the US EPA¹ as material that is uniform in texture and appearance, was installed at one time, and is unlikely to consist of more than one type or formulation of material. The homogeneous materials are determined by visual examination, available information on the phases of the construction and prior renovations.

The following materials were sampled:

- All friable materials historically known to contain asbestos, regardless of year of installation, not identified in previous reports;
- Friable materials previously sampled in insufficient quantity to conclude the materials are non-asbestos, in accordance with the requirements of O.Reg. 278/05;
- Friable materials previously reported to contain less than 1% asbestos, if sampled prior to the Ministry of Labour defining an asbestos-containing material as a material containing contains 0.5 percent or more asbestos by weight;
- Non-friable acoustic ceiling tiles;
- Non-friable vinyl floor tiles and mastic.

The following materials were **not** sampled:

- Materials previously identified in previous reports provided as asbestos-containing;
- Materials previously confirmed to be non-asbestos in accordance with O.Reg. 278/05;
- Unless damaged the following materials were not sampled: plaster, drywall joint compound, mastic, window caulking, roofing materials, vinyl sheet flooring. Materials not sampled are assumed to contain asbestos.
- Materials where sampling poses an inherent, imminent danger to the Assessor such as high voltage wiring, materials present at heights greater than 12 feet, or those in confined spaces. These materials are assumed to be asbestos-containing.

In some cases, manufactured products such as asbestos cement pipe are visually identified without sample confirmation.

¹ Environmental Protection Agency



Pinchin submits the bulk samples to a NVLAP² accredited laboratory for analysis. The analysis is performed in accordance with Test Method EPA/600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials, July 1993.

The asbestos analysis is completed using a stop positive approach. Only one result of greater than the regulated criteria (0.5%) is required to determine that a material is asbestos-containing, but all samples must be analyzed to conclusively determine that a material is non-asbestos. The laboratory stops analyzing samples from a homogeneous material once a result greater than the regulated criteria is detected in any of the samples of that material. All samples of a homogeneous material are analyzed if no asbestos is detected. In some cases, all samples are analyzed in the sample set regardless of result. Where building materials are described in the report as non-asbestos, or described as containing no asbestos, this is subject to the limitations of the analytical method used, and should be understood to mean no asbestos was detected.

Asbestos materials are evaluated in order to make recommendations regarding remedial work. The priority for remedial action is based on several factors:

- friability (friable or non-friable).
- condition (good, fair, poor, debris, based on definitions in the SOP).
- accessibility (ranking from accessible to all building users to inaccessible).
- visibility (whether the material is obscured by other building components).
- efficiency of the work (for example, if damaged ACM is being removed in an area, it may be most practical to remove all ACM in the area even if it is in good condition).

This includes friability, condition and efficiency and practicality of the work.

1.3 Lead

Pinchin collected samples of damaged paint not identified in a previous report. Drawings included show sample locations.

Analysis for lead in paints or surface coatings is performed in accordance with EPA Method No. 3050B/Method No. 7420; flame atomic absorption at an accredited laboratory.

For this report, all paints containing lead at a concentration 0.1% or greater are discussed. Paint was evaluated for condition.

² National Voluntary Laboratory Accreditation Program

Lead building products (e.g. batteries, lead sheeting, flashing) are identified by visual observation only.

1.4 Silica

Pinchin identifies building materials suspected of containing crystalline silica (e.g. concrete, cement, tile, brick, masonry, mortar) by knowledge of current and historic applications and visual inspection only.

Pinchin does not perform sampling of these materials for laboratory analysis of crystalline silica content.

1.5 Mercury

Building materials/products/equipment (e.g. thermostats, barometers, pressure gauges, light tubes), suspected to contain mercury were identified by visual inspection only. Dismantling of equipment suspected of containing mercury was not performed. Sampling of these materials for laboratory analysis of mercury content was not performed.

Mercury spills or damaged mercury-containing equipment was recorded where observed.

1.6 Polychlorinated Biphenyls

Pinchin determines the potential for light ballast and wet transformers to contain PCBs based on the age of the building, a review of maintenance records and examination of labels or nameplates on equipment, where present and accessible. The information is compared to known ban dates of PCBs and Environment Canada publications.

Dry type transformers are assumed to be free of dielectric fluids and hence non-PCB.

Pinchin records spills or leakage of suspect PCB-containing fluids where observed or identified in historical documents.

Fluids (mineral oil, hydraulic or Askaral) in transformers or other equipment are not sampled for PCB content.

Non-liquid forms of PCBs (i.e. sealants or caulking) are not sampled for PCB content.

1.7 Visible Mould

Pinchin identifies the presence of mould if visibly present in a significant quantity on exposed building surfaces. If any mould growth is concealed within wall cavities it is not addressed in this survey.

APPENDIX IV
Photographs



Designated Substances Survey Report

32 Division
30 Ellerslie Ave., Toronto, ON
The City of Toronto

December 4, 2015

Pinchin File: 103037

Appendix IV



ACT03



VFT03



Designated Substances Survey Report

32 Division
30 Ellerslie Ave., Toronto, ON
The City of Toronto

December 4, 2015

Pinchin File: 103037

Appendix IV



VFT04



VFT05



Designated Substances Survey Report

32 Division
30 Ellerslie Ave., Toronto, ON
The City of Toronto

December 4, 2015

Pinchin File: 103037

Appendix IV



VFT06

APPENDIX V
Survey Form

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
0-00	Exterior	Roof	Roofing Material	Asbestos	Not Sampled	ACM Assumed	20000 sf	Good	
0-00	Exterior	Windows	Window Caulking	Asbestos	Not Sampled	ACM Assumed	2000 sf	Good	
Basement									
B-001	Stairs	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-001	Stairs	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	600 sf	Good	
B-001	Stairs	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
B-002	Corridor	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-002	Corridor	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-002	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
B-003	Boiler Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-003	Boiler Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-003	Boiler Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-003	Boiler Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
B-003	Boiler Room	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
B-003	Boiler Room	Mechanical	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation on domestic hot water tank
B-004	Mechanical Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-004	Mechanical Room	Floor	Paint	Lead	2015-L001	0.084	N/A	N/A	Grey paint on concrete floor
B-004	Mechanical Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-004	Mechanical Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-004	Mechanical Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
B-004	Mechanical Room	Piping	Parging Cement Pipe Insulation	Asbestos	1998 Sample 1	40 % Chrysotile	8 fittings	Good	
B-004	Mechanical Room	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
B-005	Mechanical Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-005	Mechanical Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-005	Mechanical Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-006	Janitor's Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-006	Janitor's Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-006	Janitor's Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	150 sf	Good	NAC
B-007	Washroom	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-007	Washroom	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-007	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
B-008	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
B-008	Washroom	Walls	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
B-008	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	NAC
B-009	Storage Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-009	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-009	Storage Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	50 sf	Good	NAC
B-010	Fan Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-010	Fan Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-010	Fan Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
B-010	Fan Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
B-011	Storage Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-011	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-011	Storage Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2015-A0004A-C	None Detected	N/A	N/A	ACT-02: 24"x48" Random hole pattern
B-012	Storage Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-012	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-012	Storage Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-013	Waiting Area	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-013	Waiting Area	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-013	Waiting Area	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-014	Range	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-014	Range	Walls	Tectum Tile	N/A	N/A	N/A	N/A	N/A	
B-014	Range	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-015	Elevator	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0002A-C	None Detected	N/A	N/A	VFT-02: 12" x 12" white with beige and brown smears
B-015	Elevator	Walls	Metal	N/A	N/A	N/A	N/A	N/A	
B-015	Elevator	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-016	Stairwell	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-016	Stairwell	Walls	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
B-016	Stairwell	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-016	Stairwell	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	250 sf	Good	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
B-017	Corridor	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	Good	VFT-01: 12" x 12" beige with black and white streaks
B-017	Corridor	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-017	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
B-017	Corridor	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
B-018	Fan Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-018	Fan Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-018	Fan Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-018	Fan Room	Piping	Parging Cement Pipe Insulation	Asbestos	1998 Sample 1	40 % Chrysotile	22 fittings	Good	
B-019	Memo Storage	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-019	Memo Storage	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-019	Memo Storage	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-019	Memo Storage	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
B-020	Storage Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-020	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-020	Storage Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-020	Storage Room	Piping	Parging Cement Pipe Insulation	Asbestos	1998 Sample 1	40 % Chrysotile	12 fittings	Good	
B-020	Storage Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
B-020	Storage Room	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
B-021	Caretaker's Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-021	Caretaker's Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
B-021	Caretaker's Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
B-022	Electrical Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-022	Electrical Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-022	Electrical Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-023	Corridor	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-023	Corridor	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-023	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
B-024	Mechanical Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-024	Mechanical Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-024	Mechanical Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-024	Mechanical Room	Piping	Parging Cement Pipe Insulation	Asbestos	1998 Sample 1	40 % Chrysotile	2 fittings	Good	
B-024	Mechanical Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
B-024	Mechanical Room	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
B-025	Supplies	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-025	Supplies	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
B-025	Supplies	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
B-026	Stairwell	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-026	Stairwell	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	700 sf	Good	
B-026	Stairwell	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	250 sf	Good	NAC
B-027	Transe Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards

Summary of Findings

Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C).
Added lead sample for paint in Location B-04 (2015-L001)

Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
B-027	Transe Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
B-027	Transe Room	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	NAC
B-028	Corridor	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-028	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
B-028	Corridor	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
B-029	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-029	Office	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-029	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
B-030	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-030	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0003A-C	None Detected	N/A	N/A	VFT-03: 12" x 12" black
B-030	Office	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-030	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
B-031	Vestibule	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-031	Vestibule	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
B-031	Vestibule	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
B-032	Stairwell	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-032	Stairwell	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
B-032	Stairwell	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	NAC
B-033	Storage Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-033	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
B-033	Storage Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-033	Storage Room	Piping	Parging Cement Pipe Insulation	Asbestos	1998 Sample 1	40 % Chrysotile	6 fittings	Good	
B-034	Property Office	Floor	N/A	N/A	N/A	N/A	N/A	N/A	
B-034	Property Office	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-034	Property Office	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-034	Property Office	Piping	Parging Cement Pipe Insulation	Asbestos	1998 Sample 1	40 % Chrysotile	9 fittings	Good	
B-035	Corridor	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-035	Corridor	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-035	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
B-036	Exercise Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-036	Exercise Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-036	Exercise Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
B-036	Exercise Room	Piping	Parging Cement Pipe Insulation	Asbestos	1998 Sample 1	40 % Chrysotile	3 fittings	Good	
B-037	Exercise Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
B-037	Exercise Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-037	Exercise Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
B-038	Storage Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
B-038	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-038	Storage Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2015-A0004A-C	None Detected	N/A	N/A	ACT-02: 24"x48" Random hole pattern
B-039	Locker Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
B-039	Locker Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
B-039	Locker Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2015-A0004A-C	None Detected	N/A	N/A	ACT-02: 24"x48" Random hole pattern
Main Floor									
1-040	Stairwell	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-040	Stairwell	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
1-040	Stairwell	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	NAC
1-041	Corridor	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-041	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	2000 sf	Good	
1-041	Corridor	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
1-041	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-042	Training SGT	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-042	Training SGT	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
1-042	Training SGT	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-042	Training SGT	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-042	Training SGT	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-042	Training SGT	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-043	Conference Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-043	Conference Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
1-043	Conference Room	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	700 sf	Good	
1-043	Conference Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
1-043	Conference Room	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-044	Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-044	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
1-044	Office	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	700 sf	Good	
1-044	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-044	Office	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-045	Inspectors Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-045	Inspectors Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
1-045	Inspectors Office	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
1-045	Inspectors Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-045	Inspectors Office	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-045	Inspectors Office	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-046	Superintendent	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-046	Superintendent	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
1-046	Superintendent	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
1-046	Superintendent	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-046	Superintendent	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-046	Superintendent	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-047	Closet	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
1-047	Closet	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	150 sf	Good	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
1-047	Closet	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	20 sf	Good	NAC
1-047	Closet	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-047	Closet	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-048	Washroom	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
1-048	Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-048	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	80 sf	Good	NAC
1-049	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-049	Washroom	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-049	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	50 sf	Good	NAC
1-050	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-050	Washroom	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
1-050	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	80 sf	Good	NAC
1-051	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-051	Washroom	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	600 sf	Good	
1-051	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	150 sf	Good	NAC
1-052	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-052	Washroom	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	700sf	Good	
1-052	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	NAC
1-053	Administration	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-053	Administration	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	600 sf	Good	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards

Summary of Findings

Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C).
 Added lead sample for paint in Location B-04 (2015-L001)

Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
1-053	Administration	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
1-053	Administration	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-054	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-054	Washroom	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-054	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	50 sf	Good	NAC
1-055	Vestibule	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-055	Vestibule	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-055	Vestibule	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-056	Vestibule	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-056	Vestibule	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-056	Vestibule	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	50 sf	Good	NAC
1-057	Lobby	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-057	Lobby	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
1-057	Lobby	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	NAC
1-060	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
1-060	Washroom	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
1-060	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
1-061	Corridor	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-061	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	500 sf	Good	
1-061	Corridor	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
1-061	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-061	Corridor	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-061	Corridor	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-062	Parade Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-062	Parade Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
1-062	Parade Room	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
1-062	Parade Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-063	Inspector Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0005A-C	None Detected	N/A	N/A	VFT-04: 12" x 12" Off white with white and black streaks
1-063	Inspector Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	500 sf	Good	
1-063	Inspector Office	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-063	Inspector Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-063	Inspector Office	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-064	Closet	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0005A-C	None Detected	N/A	N/A	VFT-04: 12" x 12" Off white with white and black streaks
1-064	Closet	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	
1-064	Closet	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	20 sf	Good	NAC
1-065	Washroom	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0005A-C	None Detected	N/A	N/A	VFT-04: 12" x 12" Off white with white and black streaks
1-065	Washroom	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	150 sf	Good	
1-065	Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	150 sf	Good	
1-065	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	50 sf	Good	NAC
1-065	Washroom	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards

Summary of Findings

Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C).
 Added lead sample for paint in Location B-04 (2015-L001)

Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
1-066	Traffic Response	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
1-066	Traffic Response	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
1-066	Traffic Response	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-066	Traffic Response	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-066	Traffic Response	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-067	Community Response	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0005A-C	None Detected	N/A	N/A	VFT-04: 12" x 12" Off white with white and black streaks
1-067	Community Response	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-067	Community Response	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-067	Community Response	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-067	Community Response	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-068	Community Response	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
1-068	Community Response	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	500 sf	Good	
1-068	Community Response	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	500 sf	Good	
1-068	Community Response	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-068	Community Response	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
1-069	CRU SGT	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
1-069	CRU SGT	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	500 sf	Good	
1-069	CRU SGT	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	500 sf	Good	
1-069	CRU SGT	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-069	CRU SGT	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
1-070	Stairwell	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-070	Stairwell	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
1-070	Stairwell	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	NAC
1-071	Report Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
1-071	Report Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-071	Report Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
1-072	Report Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-072	Report Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-072	Report Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-073	Property Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-073	Property Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-073	Property Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-074	Gun Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-074	Gun Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	600 sf	Good	
1-074	Gun Room	Ceiling	Texture Finish	Asbestos	1998 Sample 5, 2006 Sample 11087B42-03 to 06	None Detected	N/A	N/A	NAC
1-075	General Office	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
1-075	General Office	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
1-075	General Office	Ceiling	Texture Finish	Asbestos	1998 Sample 5, 2006 Sample 11087B42-03 to 06	None Detected	N/A	N/A	NAC
1-076	Corridor	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards

Summary of Findings

Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C).
 Added lead sample for paint in Location B-04 (2015-L001)

Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
1-076	Corridor	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
1-076	Corridor	Ceiling	Texture Finish	Asbestos	1998 Sample 5, 2006 Sample 11087B42-03 to 06	None Detected	N/A	N/A	NAC
1-077	Elevator Vestibule	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-077	Elevator Vestibule	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
1-077	Elevator Vestibule	Ceiling	Texture Finish	Asbestos	1998 Sample 5, 2006 Sample 11087B42-03 to 06	None Detected	N/A	N/A	NAC
1-078	Stairwell	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-078	Stairwell	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	600 sf	Good	
1-078	Stairwell	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	NAC
1-079	Janitor's Room	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-079	Janitor's Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-079	Janitor's Room	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
1-080	Vestibule	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-080	Vestibule	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
1-080	Vestibule	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
1-081	Janitor's Room	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-081	Janitor's Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-081	Janitor's Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
1-082	Forensic Lab	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-082	Forensic Lab	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
1-082	Forensic Lab	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	NAC
1-083	Janitor's Room	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
1-083	Janitor's Room	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
1-083	Janitor's Room	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
1-084	Identification	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-084	Identification	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
1-084	Identification	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-085	Booking Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-085	Booking Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	600 sf	Good	
1-085	Booking Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-085	Booking Room	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
1-086	Corridor	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-086	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	900 sf	Good	
1-086	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
1-087	Bullpen	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-087	Bullpen	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-087	Bullpen	Ceiling	Texture Finish	Asbestos	1998 Sample 5, 2006 Sample	None Detected	N/A	N/A	NAC
1-088	Washroom	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-088	Washroom	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
1-088	Washroom	Ceiling	Texture Finish	Asbestos	1998 Sample 5, 2006 Sample 11087B42-03 to 06	None Detected	N/A	N/A	NAC
1-089	Cells	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-089	Cells	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-089	Cells	Ceiling	Texture Finish	Asbestos	1998 Sample 5, 2006 Sample 11087B42-03 to 06	None Detected	N/A	N/A	NAC
1-090	Mechanical Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-090	Mechanical Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-090	Mechanical Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
1-091	Sally port	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-091	Sally port	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-091	Sally port	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
1-092	Sally port	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-092	Sally port	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-092	Sally port	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
1-092	Sally port	Piping	Parging Cement Pipe Insulation	Asbestos	1998 Sample 1	40 % Chrysotile	1 Fitting	Good	
1-093	Washroom	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-093	Washroom	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-093	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	150 sf	Good	NAC
1-094	Garage	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-094	Garage	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
1-094	Garage	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
1-094	Garage	Piping	Parging Cement Pipe Insulation	Asbestos	1998 Sample 1	40 % Chrysotile	75 fittings	Good	
1-094	Garage	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canva jacketing
1-095	Storage Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
1-095	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-095	Storage Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
1-096	Storage Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-096	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-096	Storage Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
1-097	Storage Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
1-097	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-097	Storage Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
1-098	Storage Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
1-098	Storage Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-098	Storage Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
1-099	Lunch Room	Floor	Concrete	N/A	N/A	N/A	N/A	N/A	
1-099	Lunch Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
1-099	Lunch Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
Second Floor									
2-100	Stairwell	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
2-100	Stairwell	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-100	Stairwell	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-101	Lunch Room	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
2-101	Lunch Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-101	Lunch Room	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	2000 sf	Good	
2-101	Lunch Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-101	Lunch Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
2-101	Lunch Room	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
2-102	Domestic Violence	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-102	Domestic Violence	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-102	Domestic Violence	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-102	Domestic Violence	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2015-A0006A-C	None Detected	N/A	N/A	ACT-03: 24"x48" Random fleck and hole
2-102	Domestic Violence	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
2-102	Domestic Violence	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
2-102	Domestic Violence	Other	Thermostat	Mercury	N/A	Mecury containing	1 unit	N/A	
2-103	Showers	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
2-103	Showers	Walls	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
2-103	Showers	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	NAC
2-104	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
2-104	Washroom	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	600 sf	Good	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
2-104	Washroom	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	NAC
2-105	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
2-105	Washroom	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	600 sf	Good	
2-105	Washroom	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	NAC
2-106	Finishing Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-106	Finishing Room	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	600 sf	Good	
2-106	Finishing Room	Ceiling	Plaster	Asbestos	Not Sampled	ACM Assumed	250 sf	Good	NAC
2-107	Plain Clothes	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0008A-C	None Detected	N/A	N/A	VFT-06:12" x 12" beige with brown smears
2-107	Plain Clothes	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
2-107	Plain Clothes	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
2-107	Plain Clothes	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2015-A0006A-C	None Detected	N/A	N/A	ACT-03: 24"x48" Random fleck and hole
2-108	Plain Clothes	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-108	Plain Clothes	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	500 sf	Good	
2-108	Plain Clothes	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	150 sf	Good	NAC
2-109	Interview Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0008A-C	None Detected	N/A	N/A	VFT-06:12" x 12" beige with brown smears
2-109	Interview Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
2-109	Interview Room	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A	No ceiling found
2-110	Corridor	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
2-110	Corridor	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-110	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
2-110	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2015-A0006A-C	None Detected	N/A	N/A	ACT-03: 24"x48" Random fleck and hole
2-110	Corridor	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
2-111	Locker Room	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
2-111	Locker Room	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-111	Locker Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	2000 sf	Good	
2-111	Locker Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-111	Locker Room	Piping	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with canvas jacketing
2-111	Locker Room	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
2-112	Elevator Lobby	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
2-112	Elevator Lobby	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
2-112	Elevator Lobby	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-113	Stairwell	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
2-113	Stairwell	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-113	Stairwell	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-114	Corridor	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
2-114	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-114	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-114	Corridor	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
2-115	Interview Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0007A-C	None Detected	N/A	N/A	VFT-05:12" x 12" blue with white smears
2-115	Interview Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
2-115	Interview Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
2-116	CIB	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0008A-C	None Detected	N/A	N/A	VFT-06:12" x 12" beige with brown smears
2-116	CIB	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-116	CIB	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	2015-A0006A-C	None Detected	N/A	N/A	ACT-03: 24"x48" Random fleck and hole
2-117	Detectives	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-117	Detectives	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	500 sf	Good	
2-117	Detectives	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-118	Interview Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0007A-C	None Detected	N/A	N/A	VFT-05:12" x 12" blue with white smears
2-118	Interview Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
2-118	Interview Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
2-119	Stairwell	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
2-119	Stairwell	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
2-119	Stairwell	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-120	Clerks	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
2-120	Clerks	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-120	Clerks	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-121	SGT Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-121	SGT Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	700 sf	Good	
2-121	SGT Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-122	Interview Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0007A-C	None Detected	N/A	N/A	VFT-05:12" x 12" blue with white smears

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
2-122	Interview Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
2-122	Interview Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
2-123	Interview Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0007A-C	None Detected	N/A	N/A	VFT-05:12" x 12" blue with white smears
2-123	Interview Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
2-123	Interview Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
2-124	Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
2-124	Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
2-124	Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-125	Staff Sgt	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-125	Staff Sgt	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	700 sf	Good	
2-125	Staff Sgt	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-126	Street Crime	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
2-126	Street Crime	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	900 sf	Good	
2-126	Street Crime	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-127	Janitor Closet	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
2-127	Janitor Closet	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
2-127	Janitor Closet	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	20 sf	Good	NAC
2-128	Closet	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-128	Closet	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
2-128	Closet	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	20 sf	Good	NAC

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
2-129	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
2-129	Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	300 sf	Good	
2-129	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	50 sf	Good	NAC
2-130	D/SGT	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-130	D/SGT	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-130	D/SGT	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-131	Crime Management	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-131	Crime Management	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-131	Crime Management	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-132	Corridor	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	
2-132	Corridor	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	2000 sf	Good	
2-132	Corridor	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-132	Corridor	Duct	Insulation - Fiberglass	N/A	N/A	N/A	N/A	N/A	Fiberglass insulation with foil jacketing
2-133	Change Room	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
2-133	Change Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
2-133	Change Room	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	200 sf	Good	
2-133	Change Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-134	Planning Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0001A-C	None Detected	N/A	N/A	VFT-01: 12" x 12" beige with black and white streaks
2-134	Planning Office	Floor	Vinyl Floor Tiles (VFT)	Asbestos	2015-A0008A-C	None Detected	N/A	N/A	VFT-06: 12" x 12" beige with brown smears
2-134	Planning Office	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards

Summary of Findings

Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C).
 Added lead sample for paint in Location B-04 (2015-L001)

Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
2-134	Planning Office	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1700 sf	Good	
2-134	Planning Office	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-138	Washroom	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
2-138	Washroom	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
2-138	Washroom	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	400 sf	Good	
2-138	Washroom	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	600 sf	Good	NAC
2-139	Woman's Locker Room	Floor	Ceramic Tile	N/A	N/A	N/A	N/A	N/A	
2-139	Woman's Locker Room	Walls	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	500 sf	Good	
2-139	Woman's Locker Room	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	1000 sf	Good	
2-139	Woman's Locker Room	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
2-140	Interview Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-140	Interview Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
2-140	Interview Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	NAC
2-141	Video Room	Floor	Carpet	N/A	N/A	N/A	N/A	N/A	
2-141	Video Room	Walls	Concrete Block	N/A	N/A	N/A	N/A	N/A	
2-141	Video Room	Ceiling	Drywall Joint Compound (DJC)	Asbestos	Not Sampled	ACM Assumed	100 sf	Good	
2-142	Stairwell	Floor	Terazzo	N/A	N/A	N/A	N/A	N/A	

APPENDIX V - Survey Form

Building Address	30 Ellerslie Road, Toronto, Ontario			Date(s) of Current Survey:	June 4, 2015				
Building Name	32 Division			Organization Completing Survey	Pinchin Ltd. - John Edwards				
Summary of Findings Added asbestos samples for VFT01 (2015-A0001A-C), VFT02 (2015-A0002A-C), VFT03 (2015-A0003A-C), VFT04 (2015-A0005A-C), VFT05 (2015-A0007A-C), VFT06 (2015-A0008A-C), ACT02 (2015-A0004A-C) and ACT03 (2015-A0006A-C). Added lead sample for paint in Location B-04 (2015-L001)									
Location Number	Location Name	Building System	Material Observed	Potential Hazardous Material	Sample ID	Analytical Result	Quantity	Condition	Notes / Recommended Actions
2-142	Stairwell	Walls	Plaster	Asbestos	Not Sampled	ACM Assumed	800 sf	Good	
2-142	Stairwell	Ceiling	Acoustic Ceiling Tiles (ACT)	Asbestos	11087-B42-01 & 02 and sample 4	None Detected	N/A	N/A	ACT-01: 24"x48" Widthwise fissure and pinhole
Surveyor's Field Notes									
NAC - No access above ceiling									