

Date September 23, 2026

Sent via Email (2 pages)

**ADDENDUM NO. 2
REQUEST FOR TENDER (RFT) WORK ASSIGNMENT NO. CREM-PMO-26-010
IN ACCORDANCE WITH**

**REQUEST FOR SUPPLIER QUALIFICATION (RFSQ Doc3512316731),
Category: 1**

CLOSING DATE: October 2, 2026, AT 12:00 PM (LOCAL TORONTO TIME)

Technology Services Division-Office Space Interior Alterations at 703 Don Mills Rd., as detailed in the consultant's drawings/specifications documents and according to the City's Contract.

REVISED CLOSING DATE: From **September 25, 2026, To October 2, 2026 12:00 PM**

Please refer to the above Request for Quotation (RFQ) document in your possession and be advised of the following:

QUESTIONS:

1. We received a question from one of the drywall subcontractors regarding the wall and ceiling assemblies.
 - After reviewing the issued architectural documents, we could not identify a detailed assembly schedule or specification covering the required drywall, metal studs, insulation, and ceiling assemblies. Addendum 1 clarified the extent of finishes and painting but did not appear to provide additional assembly details.
 - Could you please confirm whether there is an additional wall/ceiling assembly schedule, specification, or other document available for this scope?

Answer: THERE ARE NO NEW PARTITIONS OR CEILINGS IN THE SOW

2. On the finishing plan A4.0 painting, carpet and rubber base, millwork, window film, exobords are all mentioned but there are no notes regarding any of this work on the drawings. Please advise what work is required in these sections if any

Answer: there are no new finishes in the sow other than replacement work affected by construction which are to match existing

3. Is there an AV schedule, there appears to be display monitors. Are we required to supply and install these or just the blocking and electrical/communications work to make them work properly?

Answer: MONITORS ARE EXISTING TO BE RELOCATED. PROVIDE WALL BLOCKING BEHIND TVs

4. Please advise on what slab coring is required for this work. Everything looks to be fed electrically independently on each floor.


Answer: no slab coring in sow

5. Where is the location of CDC-4 distribution power panel on forth floor?
Is there any picture or photo from CDC-4 name plate and its manufacturer? We have to put a new 60 A breaker inside it to feed new UPS panel on third floor.

Answer: CDC 4 panel was investigated on site by City of Toronto Electrician, and all information should be verified with them.

6. Please provide the specifications for the special receptacle L21-30R, UPS-4/6/8, and L21-30R, UPS-10/12/14 shown on the 3rd Floor Electrical Layout, TE-3.1

Answer: L21-30R is a standard NEMA receptacle that should be readily available. Receptacles shall be commercial grade and one of the acceptable manufacturer's noted in electrical specification.



CLARIFICATIONS:

- N/A

ATTACHMENTS:

- N/A

Should you have any questions regarding this addendum contact the Roster Captain for this Category named below.

Please attach this addendum to your call document and be governed accordingly. Bidders must acknowledge receipt of all addenda in their submission in the space provided on the Bid Form as per, Section 2 in Part 3 – RFSQ Process Terms and Conditions of **RFSQ DOC No. 3512316731**. All other aspects of the call remain the same.

END OF ADDENDUM NO. 2

Roster Captain Name: Malake Abou Hmaid
Title: Sr. Project Manager, Project Management Office
Division: Corporate Real Estate Management